

BARRY COUNTY REMONUMENTATION

FEB 08 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in
BARRY
(county)

Located In: Corner Code #

1. Public Land Survey
CORNER COMMON TO
SECTIONS 20, 21, 28 & 29
BARRY TOWNSHIP

T 1N R 9W E-9
T ___ R ___
T ___ R ___
T ___ R ___



2754

Page: 1 of 1
12/17/1998 12:35P

Sandy Schondeimayer - Barry Co. LCRGR

Register of Deeds Stamp & File Number

2. Property Controlling in Section S ___ T ___ R ___
S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Brian Reynolds, in a field survey on 15 MAY, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
6													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1826 (R9W, P. 28) W. OAK 24 S18E 47 Do. 24 N26E 48
 - CONSUMERS POWER COMPANY: CHASE, DEKEYSER & ALDEN, OCT 1965, "FOUND 1/4" PIPE 0.65' E. OF 3" CHANNEL IRON CORNER POST IN CONC." NO WITNESSES GIVEN

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/4" PIPE AS RECITED IN ITEM #2 ABOVE. MEASUREMENTS TO CORRESPONDING CORNERS IN SECTION 21 INCLUDING OCCUPATION TIES CONFORM WELL WITH FOUND PIPE.
ACCEPTED FOUND PIPE AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.
WERE UNABLE TO REMOVE FOUND PIPE. LEFT FOUND PIPE IN PLACE AND SET STANDARD BARRY COUNTY REMONUMENTATION ALUMINUM CAP ON TOP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
FOUND 20d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 20" HICKORY S46°E 6.35'
FOUND 20d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 32" OAK N86°W 4.88'
FOUND "PK" IN THE SOUTH SIDE OF A 32" OAK N86°W 4.78'
FOUND 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 22" OAK N30°E 12.80'
FOUND 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 30OAK N03°E 21.59'
SOUTH FACE OF IRON FENCE CORNER POST IN CONCRETE N79°W 0.65'
CORNER LIES 0.5'± EAST OF NORTH-SOUTH FENCE
IN LINE WITH EAST-WEST TREE/FENCE LINE

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

14 Sept '98
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date DEC 15, 1998