

**SURVEY & REMONUMENTATION**

AUG 31 1994

COMMISSION

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

JUL 8 12 42 PM '94

Sandy Schindelmaier  
REGISTER OF DEEDS

For corners in BARRY  
(County)

Located In: Corner Code #

1. Public Land Survey T 1N R 9W F-4  
T BARRY TWP. SP.  
T CENTER SEC. 9
2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_
3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

**002194**

Register of Deeds Stamp & File Number

I, BRIAN REYNOLDS in a field survey on 25 FEB, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**- NOT SET BY GENERAL LAND OFFICE.**


**(NO RECORDED CORNER FOUND)**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF PREVIOUS MONUMENTATION

**-NO RECORD OF CORNER. SET AT INTERSECTION OF 1/4 LINES.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

April 19, 1994 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**-SET BARRY Co. REMONUMENTATION MONUMENT:**

N&T - N. FACE - 30" BLACK CHERRY - WEST - 15.12'

N&T - SE. FACE - 10" BLACK CHERRY - N15E - 33.63'

N&T - SE. FACE - 18" BLACK CHERRY - N50E - 39.03'

N&T - N. FACE - 30" BLACK CHERRY - S80E - 6.74'

N&T - E. FACE - 12" BOXELDER - NORTH - 26.72'

**ON FENCE EAST/WEST; FENCE NORTH 34'+/- TO THE EAST (NOT N. - S. 1/4 LINE FENCE)**

Signed by [Signature]  
Surveyor's Michigan License No. 31602

Date JUNE 20, 1994