

FEB 03 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in BARRY Located In: Corner Code #
(county)

- 1. Public Land Survey T 1N R 9W F-9
1/4 CORNER COMMON TO T _____ R _____
SECTIONS 21 & 28 T _____ R _____
BARRY TOWNSHIP T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- 4. Lot No _____, Recorded Plat _____
- 5. Private Claims _____



2755
Page: 1 of 1
12/17/1998 12:35P

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

I, Brian Reynolds, in a field survey on 15 MAY, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1826 (R9W, P. 28) HICKORY 6 N24E 17 Do. 7 S57E 6
- 2. COUNTY SURVEYOR RECORDS: LEE S. COBB, 14 APRIL, 1909 (BROWN BARRY FIELD BOOK, P. 90) "FOUND REMAINS OF STAKE, SET OAK STAKE IN PIT OF STONES & IRON AXLE" NO WITNESSES GIVEN
- 3. COUNTY SURVEYOR RECORDS: LEE S. COBB, 1912 (L. 1, P. 380) "FOUND IRON STAKE, STONE & BRICK"
- 4. COUNTY ROAD COMMISSION: ATHERLY, 26 APRIL, 1921 (DELTON & HICKORY RD. F.B., P. 36) "FOUND 1/2" IRON SHAFT" 14" W. OAK N89E 29.4' 4' W. CHERRY N45W 40.7' 30" OAK S50E 39.9'
- 5. COUNTY ROAD COMMISSION: BICKNELL, 1961 (1961 KELLOGG SCHOOL ROAD #601 F.B., P. 2) "FOUND IRON" IRON POST N45°E 31.2' COR. IRON POST EAST 25.2' 30" OAK S50°E 39.9'
- 6. CONSUMERS POWER COMPANY: CHASE, DEKEYSER & ALDEN, OCT. 1965, 3/4" PIPE OVER OLD AXLE FOUND 2.5' UNDER ROAD" 38" WHITE OAK S70°E 24.52' ANGLE IRON POST EAST 24.52' 22" W. OAK S40°E 83.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE IN MONUMENT BOX. FOUND WHITE OAK WITNESS & CORNER POST WITNESSES AS IN ITEMS #4 & #5 ABOVE. FOUND ALL WITNESSES AS IN ITEM #6 ABOVE. ACCEPTED FOUND PIPE AS PERPETUATION OF CORNER POSITION BY LEE S. COBB AS FURTHER PERPETUATED BY ROAD COMMISSION AND CHASE, DEKEYSER & ALDEN. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT IN MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP. SOUTHWEST CORNER OF AN ANGLE IRON FENCE CORNER POST IN CONCRETE EAST 24.52' SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST ROOT OF A 48" OAK S59°E 41.04' SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST ROOT OF A 10" QUAD CHERRY S32°E 51.16' SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 40" OAK S14°E 114.04' SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 48" OAK S21°E 84.22' CORNER LIES 1± EAST OF PAINTED NORTH-SOUTH CENTERLINE IN LINE WITH TREE LINE EAST

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

14 Sept. '98

BR

BRIAN REYNOLDS

COUNTY SURVEYOR



Signed by [Signature]

Surveyor's Michigan License No. 31602

Date DEC 15, 1998