

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

BARRY Located In: Corner Code #
(County)
BARRY TOWNSHIP
1. Public Land Survey T 1N R 9W G-3
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____



2803

Page: 1 of 1
12/07/1999 08:3

Darla K. Burghdoff - Barry Co. LCRGR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on MAY 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.
SURVEY BY BRIAN REYNOLDS, P.S. NO. 31602, NOVEMBER 1992
DESCRIPTION OF CORNER AND WITNESSES NOT LISTED.

SURVEY &
REMONUMENTATION

APR 04 2000

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON WITH CAP ON SOUTH SIDE OF 4" STEEL POST
SET IN ROCKS WITH REMAINS OF FENCES RUNNING N,E & W, CAP NOT READABLE.


WITH NO OTHER EVIDENCE AVAILABLE OR FOUND, I ACCEPTED FOUND 1/2" IRON
AS BEST EVIDENCE OF ORIGINAL CORNER.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 SEPT 99 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BARRY COUNTY REMONUMENTATION STAKE AND CAP
ON SOUTH SIDE OF 4" STEEL POST IN ROCKS
16" OAK, N40°E 36.40 FEET, SET BARRY COUNTY SPOTTER
8" MAPLE, N69°E 39.57 FEET, SET BARRY COUNTY SPOTTER
20" OAK, N20°W 31.28 FEET, SET BARRY COUNTY SPOTTER
28" OAK, N73°W 26.68 FEET, SET BARRY COUNTY SPOTTER
FENCE LINES (SOMEWHAT FALLEN) NORTH, EAST & WEST.



Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date Nov 2 1999