

SURVEY & REMONUMENTATION

FEB 17 1998



2642
Page: 1 of 1
12/16/1997 12:15P

Sandy Schondelmayer - Barry Co. LCRCR

SECTION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For Corners in BARRY COUNTY	Located In:	Corner Code #
1. Public Land Survey 1/4 COR COMMON TO SEC'S. 11 & 12 BARRY TWP.	T..1N R..9W T..... R..... T..... R..... T..... R.....K-4.....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, RAYMOND MOORED, in a field survey on JANUARY 20, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. S. SIBLEY, D.S. 1826; SET POST; W. OAK 8 N64E 32, W. OAK 16 S25W 23.
CO. SURVEYOR BOWEN (NO DATE) BROWN BARRY FIELD BOOK, PG. 85; W. OAK S301/4E 73
S. PRATT (29-MAY-83, L.2, PG. 229) FD. BY ONE US BEARING W. OAK S25W 23 TOOK
NEW BEARING W. OAK 24 S301/4E 73 LKS. STAKE FOR CORNER.

CORNER REFERENCED BY PLATS OF CEDAR POINTS (L.2, PG. 51) AND SUPV. REPLAT OF CEDAR POINT PLAT (L.3, PG. 13).
CORNER USED IN SURVEY BY WM. ROGERS, SEPT. 1964, NO WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND NO EVIDENCE OF OLD CORNER LOCATION. MONUMENTATION IN CEDAR POINT PLAT AND IN SUPV. REPLAT OF SAME TOO SPARSE TO RE-ESTABLISH CORNER. FOUND CONSIDERABLE MONUMENTATION IN 1964 WM. ROGERS SURVEY. MEASURED SOUTH ON 1/4 LINE FROM FOUND IRONS AND ESTABLISHED CORNER LOCATION PER 1964 SURVEY.
SET BARRY COUNTY REMONUMENTATION IRON W/ CAP AND ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMON PEER GROUP ON 11 March, '96 *BR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
-NAIL IN NE SIDE 20" WALNUT N40W 42.60'
-NAIL IN SW SIDE 30" MAPLE N15E 44.80'
-NAIL IN NW SIDE 20" MAPLE N45E 34.78'
-NAIL & TAG IN NE SIDE 24" WALNUT S45W 38.69'
-IN LINE WITH C/L ROADS EAST AND SOUTH
-IRONS ON SECTION LINE NORTH 379.5', 578.5', AND 802.0'

Signed by Raymond Moored
Surveyor's Michigan License No. 26463

Date 12/11/97

