

SURVEY & REMONUMENTATION

FEB 17 1998



Sandy Schondelmayer - Barry Co. LCRCR

2632

Page: 1 of 1
12/16/1997 12:15P

SECTION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For Corners in BARRY COUNTY	Located In:	Corner Code #
1. Public Land Survey 1/4 COR COMMON TO SEC'S. 1 & 12 BARRY TWP.	T..1N R..9W T..... R..... T..... R..... T..... R.....L-3.....
2. Property Controlling in Section	S.....T..... R..... S.....T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R..... S..... T..... R.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **RAYMOND MOORED**, in a field survey on **JANUARY 20, 1996** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
S.L.O. S. SIBLEY, D.S. 1826; WEST CORRECTED 39.99 SET POST; W. ASH 6 S49W 6, W. ASH 6 N62E 18 CO. SURVEYOR CRESSY (1873) BROWN BARRY FIELD BOOK, PG. 86; LIB.1, PG. 7
ACT 132 SURVEY BY R. MOORED 9 APRIL, 1996 LIB. 2, PGS 128-130.
 OTHER HISTORICAL EVIDENCE AVAILABLE.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND NAIL & RIBBON IN C/L ROAD ON OCCUP. LINE E. REMOVED NAIL AND EXCAVATED. FOUND POWDERED REMAINS OF OLD WOOD STAKE IN CIRCLE OF STONES APPROX. 1.5 FEET DEEP.
SET BARRY COUNTY REMONUMENTATION IRON W/ CAP.

I ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMON PEER GROUP ON 11 March, '96 *BR*

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
W. K. & TAG IN SE SIDE 18" HICKORY S40W 28.60'
FACE OF 4" STEEL GATE POST N50W 36.63'
W. K. & TAG IN SE TRUNK 14" QUAD HICKORY N40E 59.97'
W. K. & TAG IN WEST SIDE 14" RED OAK S40E 41.92'
C/L ROAD EAST 2' +/-
 OCCUPATION LINE EAST

Witnessed by *Raymond Moored*
 Surveyor's Michigan License No. 26463

Date 12/11/97

