

FEB 03 1999

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: **BARRY COUNTY** LOCATED IN: _____ CORNER CODE # _____

1. Public Land Survey T. 1N R. 9W M-3

SECTION COR. COMMON TO SECTION'S 1 & 12 BARRY TOWNSHIP

2. Property Controlling in section S. T. R.

3. Miscellaneous Property in Sec. S. T. R.

4. Lot No. Recorded Plat.

5. Private Claims.



2733

Page: 1 of 1
12/15/1998 08:31A

Sandy Schondelmayer - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11	12
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. BARRY COUNTY DOSSIER FOR REMONUMENTATION

G.L.O.- JOHN MULLET D.S., 1825 9R9W, P.6)
-W. ASH 24 S8-1/2W 58
-LYNN 14 N67W 83

COUNTY SURVEYOR RECORDS

-STONE IN PLACE OF STAKE 62.82 (K.M.C. L-3 TO M-3)
-STONE & IRON R.J. MANCHUM (L2, P. 219)

ALL OTHER SOURCES

-STONE POINT GLEN C. WHEATON, 24 OCT. 1913
-STONE 519.42 FOOT NORTH OF SE COR SEC. 1, (L. 2 OF PLATS P. 6)

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

DEC 7, 1998 BR
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND NO EVIDENCE OF THE ORIGINAL CORNER OF SUBSEQUENT RESTORATION.

SET BARRY COUNTY REMONUMENTATION IRON WITH CAP AT GOVERNMENT JOG DISTANCE (34.32- FEET) FROM A-3, T1N, R8W, AND ON LINE WITH FENCE LINE OCCUPATION TO NORTH AT EDGE OF SMALL LAKE.

ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE BARRY COUNTY REMON PEER GROUP ON 12-07-1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP

-PK & TAG IN NE SIDE 16" ASH N40°W 59.10'
-PK & TAG IN NE SIDE 12" ASH N80°W 47.05'
-FACE 4" STEEL FENCE POST WEST 33.62'
-PK & TAG IN NW SIDE 20" WALNUT N30°E 46.98'
-PK & TAG IN SW SIDE 14" CHERRY S15°E 67.45'
-C/L ROAD WEST 10' +/-
-A-3, JOHNSTOWN TOWNSHIP NORTH 34.32'

Raymond E. Moored

Date 12/10/98

Surveyors License No. 26463

