

FEB 03 1999

BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN:

LOCATED IN:

CORNER CODE #

ALLEGAN COUNTY

T. 1N R. 9W

M-4

1. Public Land Survey

EAST SECTION COR.

TO SECTION 12

JOHNSTOWN TOWNSHIP



2734

Page: 1 of 1

12/15/1998 08:31A

Sandy Schondelmayer - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

2. Property Controlling in section

S.....T.....R.....

S.....T.....R.....

3. Miscellaneous Property in Sec.

S.....T.....R.....

4. Lot No.....Recorded Plat.....

5. Private Claims.....

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. BARRY COUNTY DOSSIER FOR REMONUMENTATION

G.L.O., JOHN MULLETT D.S., 1825 (R9W, P.5)  
-B. OAK 30 S59W 24  
-DO. 24 N38W 22

COUNTY SURVEYOR RECORDS  
-IRON & BRICK, MANCHUM (L. 2, P. 219)

\* NO OTHER CORNER HISTORY \*

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
DEC 7, 1998 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND NO EVIDENCE OF THE ORIGINAL CORNER OF SUBSEQUENT RESTORATION.

SET BARRY COUNTY REMONUMENTATION IRON WITH CAP IN C/L ROAD AT GOVERNMENT JOG DISTANCE (30.03'-AVG.) FROM A-4, T1N, R9W.

ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY THE BARRY COUNTY REMON PEER GROUP ON 12/07/1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP

- PK & TAG IN NE SIDE 16" CHERRY N20°W 61.13'
- PK & TAG IN SE SIDE 30" ASH S50°W 27.35'
- PK & TAG IN SE SIDE 22" MAPLE N30°E 68.78'
- PK & TAG IN SW SIDE 24" OAK S40°W 44.70'
- IN C/L ROAD
- A-4, JOHNSTOWN TOWNSHIP NORTH 30.03'

Raymond Moored Date 12/10/98

Surveyors License No. 26463

