

FEB 03 1999

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN:

LOCATED IN:

CORNER CODE #

ALLEGAN COUNTY

T. 1N R. 9W

M-5

1. Public Land Survey

SECTION COR. COMMON
TO SECTION'S 12 & 13
BARRY TOWNSHIP

T. R.

T. R.

T. R.

Sandy Schondelmayer - Barry Co. LCRCR



2735

Page: 1 of 1
12/15/1998 08:31A

REGISTER OF DEEDS STAMP & FILE NUMBER

2. Property Controlling
in section

S. T. R.

S. T. R.

3. Miscellaneous
Property in Sec.

S. T. R.

4. Lot No., Recorded Plat.

5. Private Claims.

I, Raymond Moored in a field survey on Sept. 23, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. BARRY COUNTY DOSSIER FOR REMONUMENTATION

G.L.O.-JOHN MULLETT D.S., 1825 (R9W, P.5)
-MAPLE 10 S48-1/2W 50
-W. OAK 30 N43-1/2W 48

COUNTY SURVEYOR RECORDS, BOWEN, MAY 26, 1875 (L. 1, P. 88)
-FOUND STONE & ONE BEARING, TOOK NEW
-SASAFRAS 6 N37-1/4E .89

-STAKE & STONE, MANCHUM (L. 2, P. 219)

* NO OTHER CORNER HISTORY *

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
DEC 7, 1998 BR
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO EVIDENCE OF ORIGINAL CORNER OR SUBSEQUENT RESTORATION

SET BARRY COUNTY REMONUMENTATION IRON WITH CAP IN CENTERLINE OF RAOD
AT GOVERNMENT JOG DISTANCE (25.74') SOUTH OF A-5, T1N, R8W.

ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE
POSITION OF THE ORIGINAL CORNER

APPROVED BY BARRY COUNTY REMON PEER GROUP ON 12/07/1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP

- PK & TAG IN SE SIDE 24" MAPLE S40°W 64.66'
- PK & TAG IN NE SIDE 16" ASH N25°W 70.40'
- PK & TAG IN NW SIDE 12" MAPLE N30°E 41.28'
- PK & TAG IN S. SIDE 16" HICKORY N60°E 46.25'
- CENTER LINE GRAVEL Rd TO W SOUTH 25' +/-
- A-5, JOHNSTOWN TWP. NORTH 25.74'

Raymond Moored
Date 12/10/98
Surveyors License No. 26463

