

SAME AS M-13 ✓
T1N, R09W

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 4 26 PM '93

Sandy Schondelmar
REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>1N</u> R <u>8W</u> | <u>A-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

002137

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel M. Ryan, in a field survey on September 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO: 10" White Oak, N35½°E, 22 links
 12" White Oak, N27°W, 20 links

 C.P.Co.: 1" Pinch pipe with stones - 1965
 1' South of fence corner fences North, East and West
 24" Oak, N70°E, 16.46 feet
 6" Maple, N15°E, 9.55 feet
 18" Oak, N5°E, 24.30 feet

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1" Pinch Pipe - Bearings shown are magnetic.

 10" Maple, N25°E, 9.46 feet, nail in West side.
 1'± South of East & West fences, in line with fence North.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Replaced pipe with 3/4" iron rod and aluminum remonumentation cap.

 10" Maple, N25°E, 9.46 feet, nail in West side.
 5" Oak, S43°E, 32.20 feet, nail on Northeast side.
 8" Oak, S40°W, 15.43 feet, nail in East side.
 8" Oak, S56°W, 22.32 feet, nail in East side.

SURVEY & MONUMENTATION
DEC 27 2006
SECTION



Signed by Daniel M. Ryan Date September 8, 1993
 Surveyor's Michigan License No. 34975