

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

APR 14 2000

For corners in

SECTION

BARRY

Located In:

Corner Code #

(County)

BARRY TOWNSHIP  
1. Public Land Survey

T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_



**2799**  
Page: 1 of 1  
12/07/1999 08:36

Darla K. Burghdoff - Barry Co. LCRCR

2. Property Controlling  
in Section

S 3 T 1N R 9W  
S \_\_\_ T \_\_\_ R \_\_\_

005

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on MAY 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3								0				
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.

SET MEANDER POST AT 25.62 CHAINS FROM SE CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF ORIGINAL MEANDER POST FOUND.  
MEASURED I-3 TO G-3 = 5241.10' (GLO = 5221.92')  
SET MEANDER CORNER AT PRORATED DISTANCE 1697.13' (GLO = 1690.92')  
WEST OF I-3 AND ON LINE BETWEEN I-3 AND G-3.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
13 SEPT 99 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 5 FEET LONG 3/4" REBAR AND REMONUMENTATION CAP IN MARSH LAND  
4" TAMARACK, N68°E 39.80 FEET, SET SPOTTER  
4" TAMARACK, S82°E 27.07 FEET, SET SPOTTER  
3" TAMARACK, S37°E 90.67 FEET, SET SPOTTER  
4" TAMARACK, N40°W 104.22 FEET, SET SPOTTER

Signed by

Surveyor's Michigan License No. 20704

ROBERT R. CARR

