

**SURVEY & REMONUMENTATION**

NOV 04 1995

COMMISSION

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

MAY 20 2 04 PM '96

Sandy Schendelmarper  
REGISTER OF DEEDS

For corners in

BARRY  
(County)

Located In:

Corner Code ~~##~~

- |                                    |                            |                         |
|------------------------------------|----------------------------|-------------------------|
| 1. Public Land Survey              | T- <u>1N</u> R- <u>10W</u> | <u>A-2, W1/2, 6</u>     |
|                                    | T _____ R _____            | <u>PRAIRIEVILLE TWP</u> |
|                                    | T _____ R _____            | _____                   |
|                                    | T _____ R _____            | _____                   |
| 2. Property Controlling in Section | S _____ T _____ R _____    | _____                   |
|                                    | S _____ T _____ R _____    | _____                   |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____    | _____                   |
|                                    | S _____ T _____ R _____    | _____                   |

**002375**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, BASIL ANDRESS, in a field survey on FEBRUARY 3, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

THIS CORNER WAS NOT ESTABLISHED BY G.L.O.  
NO AVAILABLE RECORDS TO INDICATE THIS CORNER WAS EVER ESTABLISHED.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

EXCAVATED AN AREA 21'± SOUTH OF M-2 (T-1N, R-11W) AND FOUND PIECES OF BRICK IN AN OLD N-S FENCE LINE. A-3 IS 21.12' SOUTH OF M-3 (T-1N, R-11W). THERE WAS NO VISIBLE OCCUPATION LINE TO THE EAST. SET A STD. BARRY CO. MONUMENT (3/4" X 36" STEEL PIN W/ CAP) 21.12' SOUTH OF M-2 (T-1N, R-11W) AND ON LINE BETWEEN M-2 & M-3 (T-1N, R-11W) BOTH OF WHICH ARE STD. ALLEGAN CO. MONUMENTS.

**ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
NOV 13 1995 BR  
BRIAN REYNOLDS COUNTY SURVEYOR**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STD. BARRY CO. MON.  
M-2 (T-1N, R-11W) STD. ALLEGAN CO. MON. NORTH 21.12'  
16d & ALLEGAN CO. REMON. TAG E. SDE 30" OAK NORTH 5.37'  
16d & ALLEGAN CO. REMON. TAG SE SDE 14" BEECH N 30° E 37.30'  
16d & ALLEGAN CO. REMON. TAG SE SDE 18" ASH S 40° W 28.35'  
IRON W/ CAP SOUTH 12.98'  
1/2" IRON N 85° E 139.57'



Signed by Basil J. Andress

Date 3-29-96

Surveyor's Michigan License No. 30075

2376-A

3967-5

A. DESCRIPTION OF ORIGINAL MONUMENT . . . SUBSEQUENT RESTORATION

OCT., 1884 JOHN CRESSY, D.S.  
FOUND OLD BEARING PUT IN TILE & TOOK NEW BEARINGS  
HICKORY 10 N 50° E 46  
BUTTERNUT 5 S 73° E 36

NOV. 9, 1971 B.C.R.C.  
IRON  
28" OAK N 25° E 31.5'  
P. POLE S 88° E 35.7'  
T. POLE S 71° W 67.8'  
6" HICKORY N 11° E 16.1'  
8" HICKORY S 89° E 54.2'

APR. 18, 1972 D.A. RATEKIN, R.L.S.  
L.C.R.C. N<sup>o</sup> 45  
IRON PIPE  
28" OAK N 25° E 31.5'  
6" HICKORY N 11° E 16.1'  
P.P. S 88° E 35.7'  
8" HICKORY S 89° E 54.2'  
T.P. S 71° W 67.8'

RATEKIN WITNESS CARD  
SHOWS DIST FROM A-3 TO  
M-2 T-1N, R-11W OF  
2668.98'  
M-2 TO A-1 OF 2623.82'

DEC. 13, 1972 D.A. RATEKIN, R.L.S.  
ACT 132 SURBEY L-1, P-69

DEC. 29, 1972 J.L. KING, C.S.  
L.C.R.C. N<sup>o</sup> 60  
IRON PIPE & TILE  
CEN OF TEL. PED. EAST 11.27'  
8" HICKORY NORTH 16.50'  
24" OAK NNE 32.7'  
C/L PAVEMENT WEST 29.0'  
25' N OF C/L OF SHELP RESORT DR.  
ACT 132 SURVEY L-1, P-90

FEB. 19, 1974 A.H. MCMACHEN, R.L.S.  
ACT 132 SURVEY L-1, P-170, 171, 172, & 173

SEPT. 16, 1976 J.M. BUDZIK, R.L.S.  
ACT 132 SURVEY L-1, P-328 & 329

DEC. 30, 1976 D.A. RATEKIN, R.L.S.  
ACT 132 SURVEY L-1, P-373, 376 & 377

OCT. 2, 1979 J.H. DILLINGHAM, R.L.S.  
ACT 132 SURVEY L-1, P-556

JULY 11, 1995 J.M. BUDZIK, P.S.  
RESET A-3 FROM WITNESS ON ACT 132 SURVEY BY D.A. RATEKIN, R.L.S.  
(THESE WITNESSES ARE IDENTICAL TO THOSE SHOWN ON L.C.R.C. N<sup>o</sup> 45)  
½" IRON W/ CAP  
IRON N 80° W 62.45'  
P.K. N. SDE UTILITY POLE S 45° W 67.85'  
P.K. N. SDE UTILITY POLE N 85° E 35.73'  
NAIL & WASHER NW SDE 48" OAK N 10° E 33.01'  
M-3, T-1N, R-11W N 0°-15'-27" E 21.12'

SURVEY &  
REMONUMENTATION

MAY 20 1997

COMMISSION