

SURVEY & REMONUMENTATION

NOV 14 1995

COMMISSION

**BARRY CO. REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

MAY 20 2 04 PM '96

Sandy Schendelmarzen
REGISTER OF DEEDS

002377

Register of Deeds Stamp & File Number

BARRY (County)	Located In:	Corner Code #
1. Public Land Survey	T -1N, R -10W	A-4, W 1/2, 7
	T _____ R _____	PRAIRIEVILLE TWP
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BASIL ANDRESS, in a field survey on JANUARY 27, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
THIS CORNER WAS NOT ESTABLISHED BY G.L.O.
JAN., 1874 CRESSY, D.S.
SET IRON BOLT 10" FOR POST

**ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
Nov 13 1995 BR
BRIAN REYNOLDS COUNTY SURVEYOR**

CONT'D. ON BACK OF CERTIFICATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd 1/2" IRON IN MON. BOX
C/L RD WEST 2.5' ±
1/2" IRON IN MON. BOX M-4 T-1N, R-11W NORTH 5.72'
DIST NORTH TO A-3 2636.16'
DIST SOUTH TO A-5 2636.05'
P.P. S 60° W 78.4'
P.P. S 35° E 49.2'
18" OAK S 25° W 70.5'
REPLACED 1/2" IRON W/ BARRY CO. STD. MON. (3/4" X 24" STEEL PIN W/ CAP) ON LINE BETWEEN M-4 & M-5 (T-1N, R-11W) AND MIDWAY BETWEEN A-3 & A-5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

STD. BARRY CO. MON. IN MON. BOX
16d & ALLEGAN CO. REMON TAG S.E. SDE 18" OAK S 25° W 71.02'
16d & ALLEGAN CO. REMON TAG S.W. SDE T.P. S 35° E 49.83'
16d & ALLEGAN CO. REMON TAG N.W. SDE P.P. S 60° W 78.69'
S. EDGE STOP SIGN POST N 65° E 41.27'
C/L RD WEST 2.5'
M-4 (T-1N, R-11W) STD. ALLEGAN CO. MON. NORTH 5.66'



Signed by Basil J. Andress

Date 3-29-96

Surveyor's Michigan License No. 30075

2377-A

A. DESCRIPTION OF ORIGINAL . . . SUBSEQUENT RESTORATION

DEC. 29, 1972 J.L. KING, C.S.
L.C.R.C. N^o 59
SET ½" IRON PIPE BY PROPORTIONAL METHODS
2' EAST OF C/L OF N-S ROAD
UTILITY POLE N 45° E 31.12'
UTILITY POLE N 20° W 125.38'
UTILITY POLE S 40° W 78.42'
ACT 132 SURVEY L-1, P-90

MAY 1, 1973 A.H. MCMACHEN, R.L.S.
ACT 132 SURVEY L-1, P-166

NOV. 28, 1975 J.N. BUDZIK, R.L.S.
ACT 132 SURBEY L-1, P-328 & 329

JUNE 29, 1978 J.H. DILLINGHAM, R.L.S.
SURVEY
½" IRON
UTILITY POLE N 20° W 125.42'
UTILITY POLE S 60° W 78.40'
10" OAK S 30° W 70.82'
N.E. COR. TEL. PED. S 30° E 57.35'

OCT. 2, 1979 J.H. DILLINGHAM, R.L.S.
ACT 132 SURVEY L-1, P-552 & 553

JUNE 14, 1989 B.C.R.C.
½" IRON
P.P. S 30° E 49.17'
P.P. S 45° W 77.93'
¼" IRON NORTH 5.78'
INSTALLED MON. BOX 1993 SEASON - DON WOLF

SURVEY &
REMONUMENTATION

NOV 04 1996

COMMISSION

