

SURVEY & REMONUMENTATION

FEB 17 1998

BARRY COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in BARRY  
(county)

Located In:

Corner Code #



2603  
Page: 1 of 1  
09/16/1997 11:48

- 1. Public Land Survey T 1N R 10W A-6  
WEST 1/4 CORNER T R  
SECTION 18 T R  
PRAIRIEVILLE TOWNSHIP T R  
ON RANGE LINE
- 2. Property Controlling S    T    R     
in Section S    T    R
- 3. Miscellaneous S    T    R     
Property in Sec. S    T    R

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

- 4. Lot No   , Recorded Plat
- 5. Private Claims

I, Brian Reynolds, in a field survey on 24 JULY, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
- 2. NO MENTION OF THIS CORNER COULD BE FOUND IN THE BARRY OR ALLEGAN COUNTY SURVEYOR'S RECORDS
- 3. PRIVATE NOTES OF SURVEY BY BRIAN REYNOLDS, P.S. #31602, 20 MAY, 1994; "FOUND SPIKE"  
12" TWIN OAK S60°E 48.52' 12" CHERRY N80°E 32.99' ON N-S CENTERLINE

\*\*\* NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER. \*\*\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 60d SPIKE UNDER NORTH-SOUTH BITUMINOUS ROAD AND WITNESSES BY REYNOLDS (ITEM #2). MEASURED DISTANCE FROM A-6 TO A-7 IS 2641.67 FEET, AND MEASURED DISTANCE FROM A-6 TO A-5 IS 2641.77 FEET. A-6 LIES 0.23 FEET WEST OF A DIRECT LINE FROM M-7 TO M-5 (T1N, R11W, STANDARD CORNERS). ACCEPTED FOUND 60d SPIKE AS BEST EVIDENCE OF CORNER POSITION. REPLACED 60d SPIKE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP. FOUND NAIL IN NORTHEAST SIDE OF A 14" TWIN OAK S60°E 48.51'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP N34°E 24.40'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP N35°W 24.32'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP S15°W 52.58'  
SET 1/2" X 18" IRON W/"TRAVERSE POINT" CAP S15°E 52.13'  
FOUND NAIL IN NORTH SIDE OF A 14" CHERRY N80°E 33.02'  
CORNER IS 0.5' +/- WEST OF NORTH-SOUTH CENTERLINE  
M-6 T1N, R11W LIES SOUTH 31.62'

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 Sept. '97 BR  
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]  
Surveyor's Michigan License No 31602

Date 9/10/97