

**SURVEY & REMONUMENTATION**

**FEB 17 1998**

**SECTION**

**BARRY COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in  
BARRY  
(county)

Located In:

Corner Code #



**2605**  
Page: 1 of 1  
09/16/1997 11:48A

- 1. Public Land Survey  
WEST 1/4 CORNER  
SECTION 19  
PRAIRIEVILLE TOWNSHIP  
ON RANGE LINE  
T 1N R 10W      A-8
- 2. Property Controlling  
in Section      S \_\_\_ T \_\_\_ R \_\_\_  
                          S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous  
Property in Sec.      S \_\_\_ T \_\_\_ R \_\_\_  
                          S \_\_\_ T \_\_\_ R \_\_\_
- 4. Lot No \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

I, **Brian Reynolds**, in a field survey on **24 JULY, 1997** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
  1. THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
  2. NO RECORD OF CORNER COULD BE FOUND IN THE BARRY OR ALLEGAN COUNTY SURVEYOR RECORDS.
  3. LAND CORNER RECORDATION CERTIFICATE: #44, BY DONALD R. GILCHRIST, P.S. #13583, 11/13/72, "SET 1/2" IRON BAR ON PROPORTIONATE DISTANCE BETWEEN NORTHWEST AND SOUTHWEST CORNERS AND FROM SURVEY INFORMATION OF 1884, JOHN CRESSY, DEPUTY CO. SURVEYOR." 1/2" IRON BAR 84' NORTH OF SOUTH EDGE OF WOODS ON WEST SIDE OF ROAD 1.5'+/- WEST OF C/L ROAD THIS CORNER READILY ACCESSIBLE."
  4. COUNTY ROAD COMMISSION: MIDDLETON (FROM DEKEYSER FILES) c. 1972, "IRON" 1/2" IRON 84' NORTH OF SOUTH EDGE OF WOOD ON W. SIDE OF RD. 1.5' WEST OF C/L RD.
  5. LAND CORNER RECORDATION CERTIFICATE: #487, BY DONALD R. GILCHRIST, P.S. #13583, 2/11/94, "FD 60 P" IRON EAST 33.00' 16" POP N15°W 101.25' PK 16" W. OAK N20°E 97.05' PK GUARD POST S10°E 87.50' PK CL RD 4'+/- E
  6. BARRY COUNTY ROAD COMMISSION: DON WOLF, "INSTALLED MONUMENT BOX 1993 SEASON"
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 

FOUND 5/8" IRON SET IN CONCRETE INSIDE MONUMENT BOX. CORNER POSITION LIES IN A 15'+ FILL AREA. MEASURED DISTANCES TO FOUND A-9 (CONCRETE PLAT MONUMENT) AND FOUND A-7 (FOUND 1 1/2" SQUARE HEADED BOLT SET IN CONCRETE INSIDE MONUMENT BOX). A-8 TO A-7 2662.38'. A-8 TO A-9 2662.24'. AND A-8 BEING 3.87 WEST OF A DIRECT LINE FROM M-7 TO M-9. ACCEPTED FOUND 5/8" IRON SET IN CONCRETE, INSIDE MONUMENT BOX AS PERPETUATION OF CORNER POSITION AS ESTABLISHED BY GILCHRIST. LEFT FOUND 5/8" IRON SET IN CONCRETE, INSIDE MONUMENT BOX IN PLACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
5/8" IRON IN CONCRETE, INSIDE MONUMENT BOX.

- FOUND "PK" MOSTLY OVERGROWN IN WEST SIDE OF A 16" OAK N22°E 97.19'
- SET 1/2" X 18" IRON W"TRAVERSE POINT" CAP N47°W 16.66'
- SET 1/2" X 18" IRON W"TRAVERSE POINT" CAP S23°W 34.60'
- SET 1/2" X 18" IRON W"TRAVERSE POINT" CAP N57°E 20.28'
- SET 1/2" X 18" IRON W"TRAVERSE POINT" CAP S25°E 37.39'
- CORNER LIES 2'+/- WEST OF NORTH-SOUTH CENTERLINE
- M-8, T1N, R11W LIES SOUTH 23.71'

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

Sept. 8, '97  
BRIAN REYNOLDS

*BR*  
COUNTY SURVEYOR



Signed by *Brian Reynolds*  
Surveyor's Michigan License No. 31602

Date 9/10/97