

SURVEY & REMONUMENTATION

BARRY COUNTY REMONUMENTATION

FEB 17 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in BARRY (county)

Located In: _____ Corner Code # _____

1. Public Land Survey T 1N R 10W A-10
 WEST 1/4 CORNER T _____ R _____
 SECTION 30 T _____ R _____
 PRAIRIEVILLE TOWNSHIP T _____ R _____
 ON RANGE LINE

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No _____ Recorded Plat _____

5. Private Claims _____



2607
Page: 1 of 1
09/16/1997 11:48

Sandy Schondelmeyer - Barry Co. LCRGR

Register of Deeds Stamp & File Number _____

I, **Brian Reynolds**, in a field survey on **24 JULY, 1997** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
 - NO MENTION OF THIS CORNER COULD BE FOUND IN THE BARRY OR ALLEGAN COUNTY SURVEYOR RECORDS.
 - BARRY COUNTY ROAD COMMISSION: NO NAME, OCT. 26, 1972, "IRON" 18" ASH S20°W 33.72' NAIL 50" OAK S80°E 41.52' NAIL 3" OAK N10°W 63.35' (**THESE WITNESSES ARE FOR M-10, T1N, R11W**)
 - LAND CORNER RECORDATION CERTIFICATE: #42, BY DENNIS A. MIDDLETON, P.S. #16049, 8 NOV., 1972 "SET 1/2" IRON BAR ON PROPORTIONAL DISTANCE OF GOVERNMENT RESURVEY OF 1884" "SET 1/2" IRON BAR" N00°53'57"E (NO DISTANCE GIVEN) FROM EAST QUARTER POST OF SECTION 25, T1N, R11W, ALLEGAN COUNTY, MICH. EAST QUARTER POST OF SECTION 25, WITNESSES AS FOLLOWS 1/2" IRON PIPE 10'+/- WEST OF C/L ROAD 18" ASH S20°W 33.72' TO NAIL 3" OAK N10°W 63.35' TO NAIL 50" OAK S80°E 41.52' TO NAIL.
 - ACT 132 SURVEY BY DENNIS A. MIDDLETON, P.S. #16049, 11-10-1972, (L.1,P.59-61) RECITE SAME WITNESSES AS IN #4 ABOVE FOR M-10, T1N, R11W AND GIVE NO WITNESSES FOR A-10, T1N, R10W, ONLY A DISTANCE OF 33.75' NORTH OF M-10.
 - COUNTY ROAD COMMISSION: DON WOLF, "INSTALLED MONUMENT BOX 1993 SEASON"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NOTE THE BARRY COUNTY ROAD COMMISSION PLACED MONUMENT BOX ON THE CORNER FOR M-10 GUN PLAIN TOWNSHIP, ALLEGAN COUNTY, NOT A-10 PRAIRIEVILLE. A-10 LIES 2.5'+/- WEST OF THE ROAD. THEY ALSO HAVE WITNESSES TO THE GUN PLAIN CORNER.

FOUND 1/2" IRON WITH UNREADABLE CAP 2'+/- WEST OF THE WEST EDGE OF NORTH-SOUTH BITUMINOUS ROAD (DOSTER ROAD). FOUND WITNESSES IN ITEMS #3, #4, & #5 WITH THE ASH S20°W 33.72' MISSING. ACCEPTED FOUND 1/2" CAPPED IRON AS BEST EVIDENCE OF CORNER POSITION. REPLACED FOUND 1/2" CAPPED IRON WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP. CORNER LIES 2'+/- WEST OF THE WEST EDGE OF NORTH-SOUTH BITUMINOUS ROAD (DOSTER ROAD)

SET 20d NAIL W/REMON TAG IN THE NORTHWEST SIDE OF AN 8" MULBERRY S72°W 20.09'


SET 20d NAIL W/REMON TAG IN THE SOUTHEAST SIDE OF AN 8" MAPLE S59°W 38.40'

SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF AN 18" OAK S13°W 90.67'

SET 20d NAIL W/REMON TAG IN THE WEST ROOT OF A 50" OAK S34°E 64.26'

M-10 T1N, R11W LIES SOUTH 33.80'

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON
8 Sept. '97
 BRIAN REYNOLDS COUNTY SURVEYOR



Signed by Brian Reynolds
 Surveyor's Michigan License No. 31602

Date 9/10/97
 FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975 REVISED JANUARY, 1983 REVISED OCTOBER 1995