

MAY 22 1997

COMMISSION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED FOR RECORD

DEC 7 1 55 PM '93

Sandy Schondelmarer REGISTER OF DEEDS

002095

Register of Deeds Stamp & File Number

For corners in

Table with columns: BARRY (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

I, David F. Peabody, in a field survey on September, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O.:
W. Oak 9 N71E 69
Do 10 N24W 27

Resurvey By Cressy (Deputy Surveyor) 1884
Found Old Corner (Put in Tile)
W. Oak 22 N881/2E 59

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G.L.O. & Cressy Witnesses were gone
Found 3/4" Iron in 3" Tile (Slanted to North)
275' ± West of N1/4 Section 1, T.1S., R.11W.
1320' ± East of 1st Street

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 3/4" Iron W/Remon Cap in Center of Tile (Replacing Found 3/4" Iron)
2' ± N. of E & W Fence
In line with fence to North
20d Nail W/Barry Co. Tag, E. Side 7" Hickory S12°E 24.55'
20d Nail W/Barry Co. Tag, SE Side 15" Oak N42°E 33.10'
20d Nail W/Barry Co. Tag, E Side 15" Oak N9°W 42.44'
20d Nail W/Barry Co. Tag, NW Side 18" Oak N70°E 62.24'

Grid table with columns A-M and rows 2-13. Contains numbers 1-36.



Signed by David F. Peabody Date 11/08/93
Surveyor's Michigan License No. 25866