

SURVEY & REMONUMENTATION

1993

COMMISSION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

JUL 20 11 20 AM '93

Sandy Schondelmayer
REGISTER OF DEEDS

002026

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>1N</u> R <u>10W</u>	E-5 <u>PRAIRIEVILLE</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, BRIAN REYNOLDS, in a field survey on JULY, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER ESTABLISHED BY GENERAL LAND OFFICE DEPUTY SURVEYOR SYLVESTER SIBLEY UNDER CONTRACT DATED 5TH OCT 1826. SET POST CORNER TO SECS 8, 9, 16, 17. A W OAK 12 S45W 36
DO 17 N29E 40

RESURVEY BY CRESSY 1884. SEC COR 8, 9, 16, 17 FOUND OLD IRON & POST. PUT IN TILE & TOOK BEARINGS. B OAK 12 N79E 156 DO 10 S34E .39

RATEKIN (JUNE, 1973) L.C.R.C. #103 FOUND LARGE STONE 20" DIAM TOP, SET 1" IRON ON FLAT SIDE. KING (JUNE, 1974) L.C.R.C. #181 STONE (SET CHISEL X IN CENTER) WITNESS FROM BOTH LCRCs ON BACK OF FORM


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STONE AND 1" IRON AS DESCRIBED BY RATEKIN FOUND CHISELED "X" AS DESCRIBED BY KING CHECKED DISTANCES TO C-5 AND D-5, GOOD MATCH WITH KING'S SURVEY. CHECKED DISTANCES TO E-4, E-6 AND E-7, GOOD MATCH WITH SURVEY BY PIKE. CHECKED 16TH LINE OCCUPATION NORTH, SOUTH AND WEST, RESULTS INCONCLUSIVE. ACCEPTED POSITION OF STONE AS BEST EVIDENCE AVAILABLE FOR CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED LARGE STONE WITH STANDARD 3/4" REMONUMENTATION IRON AND ALUMINUM CAP

- 40d NAIL AND WITNESS TAG S SIDE 12" ELM N80°E 80.15'
- 40d NAIL AND WITNESS TAG NE SIDE 20" ASH S50°E 50.70'
- 40d NAIL AND WITNESS TAG SW SIDE 6" APPLE N48°W 28.79'
- 40d NAIL AND WITNESS TAG SE SIDE 3"X6" MULBERRY N30°E 17.16'



Signed by [Signature] Date JULY 19, 1993
Surveyor's Michigan License No. 31602

L.C.R.C. #103 (RATEKIN)

CENTERLINE LARGE STONE

W GUTE POST N 35°W- 23.5'

16" ASH S 50° E- 49.5'

CHANNEL IRON GUTE POST N 15 E- 22.0

10" CHERRY S 15° W (NE STALK OF CLUMP)- 36.3'

L.C.R.C. #181 (KING)

STONE (SET CHISEL X IN CENTER)

W GATE POST N 35° W 23.5'

16" ASH S 50° E, 50.50'

CHANNEL IRON GATE POST N 15° W 22.0' E OF CHANNEL

10' CHERRY S 15° W (NE STALK OF CLUMP) 37.06'