

DEC 9 2 10 PM '96

Sandy Schmalzberger  
 REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

BARRY COUNTY (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>10W</u>	<u>6-3</u>
SEC COR COMMON TO	T <u>    </u> R <u>    </u>	<u>    </u>
SEC'S 3,4,9,10 PRAIRIEVILLE	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

002442

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, RAYMOND E. MOORED, in a field survey on Feb 18, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3							●						
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O: SYLVESTER SIBLEY, D.S., 1826 (R10W, P.25)  
 DO 8 N74W 54.

CRESSY OCT.-NOV. 1884 (L2, P. 252 RESURVEY)  
 FOUND STONE & STAKE, PUT IN TILE. B. OAK 11 S88W 3  
 W. DO 8 S841/2E 161/2.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FO PR SPIKE IN CENTERLINE OF ROAD ON OCCUPATION LINE SOUTH. DIVISION OF 1/2 MILE MEASUREMENTS EAST AND SOUTH FIT 1/8 LINE OCCUPATIONS HAVING NO OTHER HISTORICAL DATA ON THIS CORNER, ACCEPTED RR SPIKE AS BEST AVAILABLE EVIDENCE OF CORNER POSITION. SET STANDARD BARRY COUNTY REMONUMENTATION IRON W/CAP.

ACT 345 BARRY COUNTY REMONUMENTATION  
 APPROVED BY PEER REVIEW AT A MEETING HELD ON  
9 OCT. '95 BR  
 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON W/CAP.  
 -ON OCCUPATION LINE TO SOUTH  
 -PK & TAG IN N SIDE 18" W. CHERRY S65E 53.34'  
 -PK & TAG IN E SIDE 30" RED OAK S5W 23.72"  
 -PK & TAG IN SW SIDE 18" W. OAK N10E 18.65'  
 -PK & TAG IN SW SIDE 20" W. OAK N50W 49.42'  
 -IN CENTERLINE E-W GRAVEL ROAD



Signed by Raymond E. Moored  
 Surveyor's Michigan License No. 26463

Date 10/7/96