

DEC 9 2 10 PM '96

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmayer
REGISTER OF DEEDS

002444

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #
1. Public Land Survey COR. COMMON TO SEC'S 9, 10, 15, 16 PRAIRIEVILLE TWP.	T <u>1</u> NR <u>10</u> W	<u>G-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

SURVEY &
REMONUMENTATION

MAY 20 1997

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

COMMISSION

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5							●						
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, RAYMOND MOORED, in a field survey on Feb. 7, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. Sylvester Sibley, D.S. 1826 (R10W, P.24) A.W. Oak 14 N73 W 34 Do 10 N.53 W 22. Cressy Oct. - Nov. 1884 (L.2, P. 252 Resurvey). Found old Stake & Stone. Put in tile. B. Oak 12 S54 1/2 W 68, Hickory 10 N66 1/2E 75.
L.C.R.C. # 223 Carroll D. Pike, Nov. 9 1977. 1/2" iron reinforcing rod 16" Hickory North 45 W 37.42' 10" oak S 30 W 35.26' 22" Hickory S 50 E 55.01'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2 REROD PER LCRC 223 BY PIKE. PHYSICAL LOCATION FIT OCCUPATION LINES NORTH AND SOUTH AND OCCUPATION LINES 1/4 AND 1/2 MILE EAST. ACCEPTED POSITION AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD REMON IRON IN PLACE OF FOUND IRON.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
9 Oct. '95
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP
-20D NAIL IN E SIDE 50" MAPLE NORTH 59.17'
-20D NAIL IN W SIDE 12" CHERRY N20 DEG E 42.21'
-20D NAIL IN E SIDE 36" MAPLE SOUTH 36.81'
-20D NAIL IN W SIDE CORNER FENCE POST 53 DEG W 34.22'



Signed by Raymond Moored
Surveyor's Michigan License No. 26463

Date 11/4/96