

APR 04 2000

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: BARRY COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T. 1N R. 10W	1-8
CORNER COMMON TO SECTION 22 & 23 PRAIRIEVILLE TOWNSHIP	T. R. T. R. T. R.
2. Property Controlling in section	S. T. R. S. T. R.
3. Miscellaneous Property in Sec.	S. T. R.
4. Lot No., Recorded Plat.		
5. Private Claims.		



2821
Page: 1 of 2
12/07/1999 08:36A

Darla K. Burghdoff - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
11 OCT 99 *BR*
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BENT 1/2" PIPE IN MON. BOX PER WITNESSES IN NO. 6 ABOVE.
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON _____

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" BARRY COUNTY REMONUMENTATION IRON WITH ALUM. CAP IN MON BOX

- NAIL IN W SIDE POWER POLE SOUTH 32.00'
- NAIL IN E SIDE 24" HICKORY N25W 41.22'
- NAIL IN SW SIDE 15" ELM N54W 64.76'
- NAIL IN N SIDE 28" CHERRY S73W 49.84'
- C/L MILO ROAD NORTH 7.3'
- ON OCCUPATION LINE TO NORTH

Raymond Moored
Date 11/10/99
Surveyors License No. 26463

