

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

APR 04 2000

SECTION

For Corners in
BARRY
(county)

Located In: Corner Code #

1. Public Land Survey
NORTH 1/4 CORNER
OF SECTION 2
PRAIRIEVILLE TOWNSHIP
ON RANGE LINE

T 1N R 10W J-1
T _____ R _____
T _____ R _____
T _____ R _____



2812
Page: 1 of 1
12/07/1999 08:36A

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

2. Property Controlling
in Section S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 22 NOVEMBER, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. GENERAL LAND OFFICE: CLOSING 1/4 CORNER NOT SET BY GENERAL LAND OFFICE SURVEY
2. COUNTY SURVEYOR RECORDS: JOHN Q. CRESSY, OCT. 7, 1884 (L.2, P. 242 RESURVEY) "PUT IN TILE, TOOK NEW BEARINGS" HICKORY 16 SOUTH 150 NO OTHER TIMBER NEAR
3. RECORDED PLATS: SUPERVISOR'S PLAT OF THE VILLAGE OF PRAIRIEVILLE, ROY. J. ROBB, P.S. #396, 14 MAY, 1931 (LIBER 2 OF PLATS, PAGE 74) REFERENCED, NO WITNESSES THE RECORDED PLAT DRAWING SHOWS THE EAST LINE OF THE "COUNTY HIGHWAY" (NORRIS ROAD, 66 FOOT R/W) IN LINE WITH J-1, BUT THE METES AND BOUNDS DESCRIPTION OF THE PLAT BOUNDARY IMPLIES THAT THE CORNER WOULD BE AT A 1°15' (AT THE NORTHWEST CORNER OF LOT 51) DEFLECTION FROM THE ROAD R/W LINE.

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DID NOT FIND ANY EVIDENCE OF PREVIOUS MONUMENTATION AT APPARENT SUBJECT CORNER LOCATION. FOUND A RAILROAD SPIKE AT INTERSECTION OF ROADS, APPARENTLY REPRESENTING J-13, T2N R10W. BASED ON EXPERIENCE WITH RETRACING OTHER PLATS AND SURVEYS BY R.J. ROBB, DISCOUNTED POSITION OF CORNER AS REPRESENTED ON THE PLAT. TRAVERSED TOWN LINE FROM G-1 TO M-1, TYING IN OCCUPATION LINES AND CORNER MONUMENTS. ANALYSIS OF RESULTING MEASUREMENTS CONFIRMED FOUND RAILROAD SPIKE AS J-13, T2N R10W. PLACED J-1 ON TOWN LINE DEFINED BY RECOVERED J-13 T2N R10W AND RECOVERED K-1 T1N R10W, AND AT A POSITION THAT BEST FIT OCCUPATION LINES AND RECOVERED CORNERS.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
- SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A UTILITY POLE S75°W 119.08'
- SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A UTILITY POLE S70°E 86.01'
- TOP CENTER OF A STEEL GUARD RAIL POST N07°W 30.50'
- TOP CENTER OF A STEEL GUARD RAIL POST N35°W 100.09'
- CORNER LIES 30'+/- EAST OF NORTH-SOUTH CENTERLINE
- J-13, T2N, R10W, LIES WEST 36.55'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 May, '96
BRIAN REYNOLDS

COUNTY SURVEYOR



Signed by
Surveyor's Michigan License No 31602

Date Dec 3, 1999