

FEB 17 1998

SECTION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in BARRY (county) Located In: Corner Code #



2610 Page: 1 of 1 09/16/1997 11:48A

- 1. Public Land Survey CORNER COMMON TO SECTIONS 1 & 2 PRAIRIEVILLE TOWNSHIP ON TOWNSHIP LINE
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No., Recorded Plat
5. Private Claims

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

I, Brian Reynolds, in a field survey on 10 DECEMBER, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

Table with columns A-M and rows 2-13 containing numbers 6-36

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1826 (R10W,P. 16) "NORTH 83.71 INTERSECTED N. BOUNDARY 49 EAST OF POST" A W. OAK 6 S71E 504 Do. 10 S1 1/2W 7.51
2. COUNTY SURVEYOR RECORDS: JOHN CRESSEY, 1884 (PRAIRIEVILLE RESURVEY L.2,P.242) "FOUND OLD BEARINGS & POST, PUT IN TILE-TOOK NEW BEARINGS" SUGAR 5 S75E 1.25 Do. 3 S38 1/2E 41
3. ALSO: WALTER HEATH, 1904 (PRAIRIEVILLE FIELD BOOK, P.9) "DUG IN CENTER OF ROAD AND FOUND TILE SET BY CRESSEY 1884, AND WITNESSED BY TWO SHADY TREES ON SOUTH SIDE OF ROAD" SUGAR 5 S75E 1.25 SUGAR 3 S38 1/2E 41 (THE TREES ARE NOW 10 OR 12 INCHES DIAMETER)
4. DYKEMA SUBDIVISION, MAY 1964, BY WENLEY Q. SMITH, P.S. #6523 (RECORDED IN LIBER 5 OF PLATS, PAGE 33) CORNER IS REFERENCED, NO WITNESSES.
\*\*\* NO OTHER INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER \*\*\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON NEAR SURFACE OF GRAVEL ROAD IN LINE WITH FENCE SOUTH. EXCAVATED WITH BACKHOE A 12' BY 5' HOLE AND FOUND TILE IN EXCELLENT CONDITION 2'+/- BELOW GRADE SURROUNDED BY SMALL STONES, WITH BOTH WITNESSES TREES BY CRESSEY. THE SUGAR MAPLE S38 1/2E REFERENCED BY CRESSY AND HEATH IS LIVING, THE SUGAR MAPLE S75E IS DEAD, THE STUMP NEARLY ROTTED THROUGH. FROM FOUND TILE TO FOUND 1/2" IRON NEAR SURFACE N83°W 1.41 FEET. ACCEPTED FOUND TILE AS CORNER BY CRESSEY. PLACED STANDARD BARRY COUNTY REMONUMENTATION MONUMENT INSIDE OF TILE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (WITH ALUMINUM CAP)
SET 20d NAIL W/PLASTIC TAG IN THE EAST ROOT OF A 40" OAK S30°W 24.71'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 12" WALNUT N60°E 28.88'
SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 14" WALNUT N07°W 31.40'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHEAST SIDE OF A 6" MAPLE S60°E 43.91'
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF THE WEST TRUNK TWIN 12" MAPLE N78°E 81.24'
STEEL FENCE POST S57°W 39.56'

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 May, 1996 BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature] Surveyor's Michigan License No. 31602

Date 9/15/97