

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

APR 04 2000

SECTION

FOR CORNERS IN: BARRY COUNTY LOCATED IN: CORNER CODE # 1. Public Land Survey T. 1N R. 10W K-7 CORNER COMMON TO SECTIONS 13, 14, 23 & 24 PRAIRIEVILLE TOWNSHIP 2. Property Controlling in section 3. Miscellaneous Property in Sec. 4. Lot No. Recorded Plat 5. Private Claims



Darla K. Burghdoff - Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

Grid table with columns A-L and rows 2-13. Contains numbers 1-36 and a black dot in cell 7J.

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON 11 OCT 99 BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON PIPE IN MON BOX PER NO'S 5 & 6 ABOVE. HICKORY SW 33.95' AND C/L ROAD 0.8' E STILL REMAIN. CORNER IS ON FAINT OCCUPATION LINE TO EAST. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER. THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" BARRY COUNTY REMON IRON WITH CAP IN MON BOX.

- NAIL & TAG IN S SIDE 18" HICKORY WEST 29.79'
-NAIL & TAG IN NW SIDE 16" HICKORY S65W 34.14'
-NAIL & TAG IN N SIDE 24" HICKORY S85E 29.05'
-NAIL & TAG IN NW SIDE 36" HICKORY N35E 48.71'
-C/L ROAD EAST 0.8' +/-
-ON FAINT TREE ROW TO EAST

Raymond Moored Date 11/10/99

Surveyors License No. 26463

