

BARRY COUNTY REMONUMENTATION APR 04 2000
 LAND CORNER RECORDATION CERTIFICATE
 FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970 SECTION

FOR CORNERS IN: BARRY COUNTY
 1. Public Land Survey LOCATED IN: T 1N R 10W CORNER CODE # K-8
 CORNER COMMON TO SECTIONS 23 & 24 PRAIRIEVILLE TOWNSHIP
 2. Property Controlling in section S.....T.....R.....
 3. Miscellaneous Property in Sec. S.....T.....R.....
 4. Lot No....., Recorded Plat.....
 5. Private Claims.....



2825
 Page: 1 of 2
 12/07/1999 08:36A

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON
 11 Oct 99 BR
 BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1-1/4" PIPE (WELL POINT) IN MON BOX PER NO. 6 ABOVE. ORIGINAL WITNESS TREE BY CRESSEY REMAINS. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER. THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON _____

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" BARRY COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX

- FD. PK IN POWER POLE S51W 53.33'
- FD. PK IN POWER POLE N23E 83.30'
- NAIL & TAG IN E SIDE 50" OAK S1W 56.92'
- NAIL & TAG IN S SIDE 26" MAPLE N66E 69.53'
- CIL MILO ROAD SOUTH 4.0'
- CIL PARKER ROAD TO SOUTH EAST 21'
- CIL PARKER ROAD TO NORTH EAST 4'
- CIL USGS BENCH MARK N55E 41.71'

Raymond Moored Date 11/10/99

Surveyors License No. 26463

