

APR 04 2000

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

SECTION

FOR CORNERS IN: BARRY COUNTY
 1. Public Land Survey LOCATED IN: T. 1N R. 10W CORNER CODE # K-9

CORNER COMMON TO SECTIONS 23, 24, 25 & 26 PRAIRIEVILLE TOWNSHIP
 T. R. T. R. T. R.

2. Property Controlling in section S. T. R. S. T. R.

3. Miscellaneous Property in Sec. S. T. R.

4. Lot No. Recorded Plat.

5. Private Claims.



2826
Page: 1 of 2
12/07/1999 09:36

Darla K. Burghdoff- Barry Co. LCRCR

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF FORM FOR CORNER HISTORY

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
11 OCT 99 BR
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE AND PIECES OF OLD TILE PER WITNESSES IN NO'S. 8 & 9 ABOVE. REMOVED PIPE AND SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP IN PLACE OF FOUND CORNER.

THIS POSITION ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON _____

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD 3/4" X 24" BARRY COUNTY REMONUMENTATION IRON WITH CAP.

- NAIL IN W SIDE 20" HICKORY NORTH 89.55'
- NAIL IN S SIDE 20" HICKORY WEST 85.63'
- NAIL IN W SIDE 14" HICKORY S6E 47.03'
- NAIL IN NE SIDE 12" HICKORY S32E 86.60'
- FD. 1/2" IRON IN CIL PARKER ROAD EAST 32.90'
- FACE OF END POST OF FENCE WEST 2.3' +/-

Raymond Moored Date 11/10/99

Surveyors License No. 26463

