

**SURVEY & REMONUMENTATION**

OCT 25 1993

COMMISSION

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

OCT 20 4 14 PM '93

Sandy Schondelmaier  
REGISTER OF DEEDS

002093

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1 N</u> R <u>10 W</u>	<u>K-11 (SW, 25)</u> <u>Prairieville</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David F. Peabody, in a field survey on August, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.:	Consumers Power Company 1965±
Y. Oak 10 N25E 42	Found 3/4" Pipe in 2" Pipe
W. Oak 9 S51E 38	At Intersection of Fences
	8" Maple S10W 25.00'
Resurvey By Cressy (Deputy Surveyor) 1884	30" Oak East 16.20'
Found Old Bearings and Post (Put in Tile)	14" Maple N5E 11.00'
W. Oak 12 N58E 27 1/2	
Do. 14 S27 1/2 E 63	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Pipe in 2" Pipe at Intersection of Fences  
Used All of 1965 Consumers Power Company Witnesses  
G.L.O. & Cressy Witnesses Were Gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remon Cap Over 3/4" Pipe  
in N&S Fence At Old Fence Corner Post  
on E'ly Edge of Swamp  
5' Tall 2" Pipe (Old Fence Corner) West 0.50' to E  
20d Nail W/Barry Co. Tag SE Side 26" Maple N5°E 11.00'  
20d Nail W/Barry Co. Tag NE Side 30" Maple S23°E 33.60'  
20d Nail W/Barry Co. Tag NW Side 10 Oak N55°E 35.80'



Signed by David F. Peabody Date 9/17/93  
Surveyor's Michigan License No. 25866

10/26/93