

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 14 8 54 AM '93

Sandy Schindelmaier
REGISTER OF DEEDS

002164

Register of Deeds Stamp & File Number

or corners in
BARRY
(County)

Located In: Corner Code #

Public Land Survey

T IN R 10W M-2
T PRAIRIEVILLE TOWNSHIP
T E. 1/4 POST SEC. 1

Property Controlling
in Section
Miscellaneous
Property in Sec.

S	T	R	_____
S	T	R	_____
S	T	R	_____
S	T	R	_____

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

BRIAN REYNOLDS in a field survey on JUL, 1993

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as crossed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- G.L.O. : W. OAK 15 S59W 42; Do. 7 N52W 55.
- JOHN CRESSEY (OCT. NOV. 1884) (PRAIRIEVILLE RESURVEY) (Pg. 247, BOOK II COUNTY SURVEYOR NOTES): "N. ON E. BOUNDARY OF SEC. 1; 7.95 LEAVE LAKE; 26.20 S. BOUNDARY OF LAKE; 34.50 LEAVE LAKE, FOUND MEANDER POST; 40.52 1/4 SEC. CORNER AT POST - FOUND OLD BEARINGS & POST; PUT IN TILE. NO TIMBER NEAR."
- PRATT (06 SEP 1888)(PG. 333 COUNTY SURVEYORS NOTES) IN A MAP OF SURVEY IN THE NW 1/4 OF SEC.6, BARRY TOWNSHIP. PRATT SHOWS A JOG BETWEEN A-2,T1N,R9W & M-2,T1N,R10W OF 3.67ch. = 242.22ft.
- WAYLAND INGERSOLL (NOV. 1967): FOUND TILE (SEE BACK OF THIS FORM FOR WIT.)

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- AFTER MEASURING JOG DISTANCE NORTH FROM M-2,T1N,R9W AND DIGGING , FOUND 3" DIA. CLAY TILE SURROUNDED WITH STONES AND IN LINE WITH NORTH-SOUTH FENCE.
- ACCEPTED CLAY TILE AS BEING WAYLAND INGERSOLL'S PERPETUATION OF M-2,T1N,R10W.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET BARRY Co. REMON. MONUMENT IN CENTER OF 3" DIA. CLAY TILE:**
- NAIL & SHINER - E. FACE - 20" OAK - N. - 25.86'
 - NAIL & SHINER - W. FACE - 20" TWIN OAK - N8W - 19.18'
 - NAIL & SHINER - S. FACE - 20" ASH - N66W - 7.93'
 - NAIL & SHINER - E. FACE - 24" TWIN OAK - S6W - 4.57'
 - PLAT COR. OF "BAY VIEW RESORT" - S47W - 26.12'
 - FENCE N. & S. - +/- 24' E. C/L PRIVATE DRIVE
 - SEC. COR. A-2,T1N,R9W 241.63' SOUTH



Recorded by [Signature]

Date DECEMBER 10, 1993

Surveyor's Michigan License No. 31602

WAYLAND INGERSOLL (NOV. 1967)

FOUND TILE:

S.E. COR. HOUSE - N45W - 60.55'

N.E. COR. HOUSE - S25W - 83.40'

TWIN 16" OAK - S2W - 4.78'

16" ASH - N80W - 8.10'

12" OAK - NSW - 19.10'

INFENCE N. & S.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

