

# BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

APR 04 2000

SECTION


For Corners in BARRY (county)  
Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey  
WEST 1/4 CORNER  
SECTION 7  
MAPLE GROVE TOWNSHIP  
ON RANGE LINE  
T 2N R 7W \_\_\_\_\_ A-4  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

2. Property Controlling in Section  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ \_\_\_\_\_

4. Lot No \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_



2784  
Page: 1 of 1  
11/16/1999 09:00A  
Daria K. Burghdoff - Barry Co. LCRCR  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 10 AUGUST, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
  - NO MENTION OF THIS CORNER COULD BE FOUND IN THE COUNTY SURVEYOR RECORDS.
  - PRIVATE SURVEY OF METES AND BOUNDS PARCEL IN SECTIONS 6 & 7, T2N R7W BY BRIAN REYNOLDS, P.S. #31602, JUNE 1992 FOUND FENCE CORNER AT APPARENT M-4 T2N R8W, SET 1/2" CAPPED IRON AT PRORATED GOVERNMENT JOG FOR A-4, T2N R7W. NOT WITNESSED.
  - PRIVATE NOTES OF SURVEY OF METES AND BOUNDS PARCEL IN SECTION 12 PROVIDED BY RAYMOND MOORED, P.S. #26463, MONUMENT AND WITNESSES NOT PROVIDED.

\*\*\* NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER \*\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND FENCE CORNER AND CAPPED IRON AS DESCRIBED IN ITEM #3 ABOVE. EXCAVATION AROUND FENCE CORNER REVEALED NO EVIDENCE OF MONUMENTATION. FROM SECTION MEASUREMENTS PROVIDED BY MOORED, IT APPEARED THAT MOORED HAD USED THE IRON INTENDED FOR A-4 AS THE CORNER FOR M-4. CONVERSATION WITH MOORED CONFIRMED THIS. MOORED STATED THAT HIS TIE WAS TO ESTABLISH RANGE LINE ONLY, AND THAT THE DIFFERENCE WOULD MAKE NO DIFFERENCE FOR HIS SURVEY. TRAVERSED RANGE LINE FROM M-1 TO M-7, FOUND THAT AVERAGE STANDARD HALF-MILE MEASURED 2653.5'. MEASURED DISTANCE FROM FENCE CORNER AT M-4 TO M-3 2656.56'; FROM FENCE CORNER AT M-4 TO M-5 2651.91'. ACCEPTED FENCE CORNER AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. SET STANDARD BARRY COUNTY MONUMENT AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.  
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 13" MAPLE N45°W 15.22'  
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 20" MAPLE N45°E 20.30'  
SET 20d NAIL W/PLASTIC TAG IN THE WEST SIDE OF A 10" MAPLE S25°W 8.00'  
SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A WOODEN FENCE POST NORTH 12.67'  
M-4, T2N, R8W, LIES SOUTH 12.80'  
CORNER LIES IN A NORTH-SOUTH FENCE LINE

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
8 June '98  
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]  
Surveyor's Michigan License No. 31602

Date 11/15/1999  
FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971