

**SURVEY &
REMONUMENTATION**

SEP 14 1999

SECTION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 7 4 26 PM '93

Sandy Schondelmarer

REGISTER OF DEEDS

For corners in

Barry
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-------------------------|---------------|
| 1. Public Land Survey | T <u>2N</u> R <u>7W</u> | <u>A-13</u> ✓ |
| | T <u>2N</u> R <u>8W</u> | <u>M-13</u> |
| | T <u>1N</u> R <u>7W</u> | <u>A-1</u> |
| | T <u>1N</u> R <u>8W</u> | <u>M-1</u> |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |

002142

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Daniel M. Ryan, in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO: 8" Beech, N48°E, 62 links
 15" B. Ash, N46°W, 45 links
 County Surveyor: Set stone, iron & glass
 no name, date or witnesses
 Robert R. Carr: Set ½" Rebar
 14" Maple, S45°W, 40.80 feet
 16" Maple, N75°W, 82.80 feet
 Corner cem. fence, N45°E, 37.50 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½" rebar in Monument box.
 20" Maple (formerly 16"), N52°W, 82.80 feet
 ½" rebar set in 1985 survey by RELS# 14766-James L. King

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced ½" rebar with 3/4" pin and aluminum remonumentation cap.
 Nail and Barry County Shiners set as follows:

South side of 30" Maple, S75°E, 71.00 feet.
 West side of 16" Elm, N15°E, 107.11 feet.
 South side of 20" Maple, N52°W, 82.81 feet.
 West side of P-pole, S70°W, 161.24 feet.



Signed by [Signature] Date September 8, 1993

Surveyor's Michigan License No. 34975