

**SURVEY & REMONUMENTATION**

NOV 9 4 1996

COMMISSION

STATE OF MICHIGAN  
COUNTY OF BARRY  
REGISTER OF DEEDS

OCT 17 3 16 PM '96

Sandra Schmalzberger  
REGISTER OF DEEDS

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #:
<u>MAPLE GROVE TOWNSHIP</u>	T <u>2N</u> R <u>7W</u>	<u>E-2</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**002411**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	15	14	13							
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, DAVID L. CLIFFORD in a field survey on SEPTEMBER 24, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1. POST SET IN ORIGINAL GOVERNMENT SURVEY BY MUSGROVE EVANS, DEPUTY SURVEYOR, IN MAY 1827 AND TWO BEARING TREES RECORDED:  
SUGAR 6" N77W 10 LKS (6.6')  
ELM 16" N69½E 36 LKS (23.8')

CONTINUED ON BACK

**ACT 345 BARRY COUNTY REMONUMENTATION**  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
OCT 9, 1995  
BRIAN REYNOLDS COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND GOT STRONG MAGNETIC READING 2' WEST OF CENTERLINE ASSYRIA ROAD ON FENCE LINE TO EAST. EXCAVATED AND FOUND STONE AND PLOW POINT. TRAVERSE OF SECTION 4 T2N R7W AND THE STANDARD TOWNSHIP LINE COMMON TO SECTION 4 SHOW STONE TO BE AT EXCELLENT POSITION FOR CORNER IN RELATION TO THE EAST-WEST ¼ LINE. THE CLOSING DISTANCE TO THE NORTH APPEARS TO BE FRAUDULENT. ACCEPTED STONE AND PLOW POINT AS CORNER AS PERPETUATED BY A.C. WILLSON, COUNTY SURVEYOR. SET STANDARD BARRY COUNTY MONUMENT BETWEEN STONE AND PLOW POINT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-2 T2N R7W  
3/4" DIAMETER STEEL BAR AND ALUMINUM CAP IMPRINTED "BARRY COUNTY REMONUMENTATION PS 31602 28409"  
NAIL AND TAG 28409 IN WEST SIDE OF 13" TWIN ASH, 194° NAZ., 107.20'  
NAIL AND TAG 28409 IN NE SIDE OF 9" POPLAR, 321° NAZ., 29.80'  
NAIL AND TAG 28409 IN EAST SIDE OF 14" TWIN ASH, 0° NAZ., 118.88'  
WEST FACE OF STEEL CAR FRAME FENCE POST, 90° NAZ., 27.72'



Signed by David Clifford  
25837

Date OCTOBER 08, 1996

Surveyor's Michigan License No. \_\_\_\_\_

2411 A

E-2 T2N R7W  
PART A CONTINUED

2. A. C. WILLSON, COUNTY SURVEYOR, USED CORNER IN APRIL 1863 IN A SURVEY RECORDED IN VOLUME 2, PAGE 48 AS "STONE AND PLOW POINT FOR POST" WITH NO WITNESSES.

3. A. C. WILLSON, COUNTY SURVEYOR, USED CORNER IN NOVEMBER 1867 IN A SURVEY RECORDED IN VOLUME 2, PAGE 189 WITH NO MENTION OF MONUMENT AND THE FOLLOWING WITNESSES:

STONE & EARTHEN N70½E 57 (37.6')  
DO S67E 58½ (38.6')

SURVEY &  
REMONUMENTATION

NOV 04 1996

COMMISSION