

APR 04 2000

BARRY COUNTY REMON.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Barry Co.	Located In:	Corner Code #
(County)	Maple Grove Twp.	E-4
1. Public Land Survey	T <u>2</u> N R <u>7</u> W	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____



2794
Page: 1 of 1
11/16/1999 09:03A

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert J Jonker, in a field survey on 5-27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8	●	9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Musgrove Evans, D.S. 1826
Tam. 6 S65°E 14'
Maple 4 N75°W 17'

A.C. Willson - Oct 16, 1867
Liber 2, Pag 185,
Fd. bearing & took new ones
Maple 8 S54°E 34'
Maple 12 N30½°E 7'

Seth Pratt, Co. Surveyor, April 17, 1890
Stake in Marsh
5" Black Ash, S84½°W 60 links (Liber 1, Pg 313)
8" Maple S54°E 34 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Started at stone at the center of Section - West West ¼ mile, found 1/8 corner stone and doubled the distance and line to set E-4, dug 4' X 4' hole 2.5' deep and found nothing.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

13 April, 99
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set std. Barry Co. Monument
Barry Co. Remon tags - N. Side 10" maple N85°E 49.13'
Barry Co. Remon tags - W. side 20" Maple S05°E 54.57'
Barry Co. Remon tags - W. side 26" Maple S35°W 16.11'
Barry Co. Remon Tags - W. side 20" Tri. N25°W 41.63'
The E-W fence is 4.5' North
Fence to South is 5' East
N-S old road bed is 5' East



Signed by Robert J. Jonker
Surveyor's Michigan License No. 21572

Date 10-7-99