

**SURVEY & REMONUMENTATION**

1993

**COMMISSION**

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmayer  
REGISTER OF DEEDS

**002060**

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #
	MAPLE GROVE	
1. Public Land Survey	T <u>2N</u> R <u>7W</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5					⊙								
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ROBERT R. CARR, in a field survey on DECEMBER 7, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
SETH PRATT, APRIL 1890; STAKE, SYCAMORE 8" N 38-3/4 W, 21-1/2 LINKS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 3/4" PIPE 3 FT SOUTH OF CENTERLINE OF EAST AND WEST ROAD AND 6 FT WEST OF CENTERLINE OF ROAD TO SOUTH.  
ACCEPTED AS PERPETUATION OF ABOVE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
PLACED STANDARD BARRY CO REMON 3/4" ROD AND ALUM CAP WITH CENTER PUNCH AND RECESSED IN BITUMINOUS SURFACE.  
3' SOUTH OF CENTERLINE OF EAST/WEST ROAD  
6' WEST OF CENTERLINE OF ROAD TO SOUTH  
NAIL AND REMON SPOTTER IN EASTERLY SIDE OF UTILITY POLE N12°W, 36.85 FT.  
NAIL AND REMON SPOTTER IN SOUTHWESTERLY SIDE OF FENCE CORNER POST  
S48°E, 51.65 FT.  
IN LINE WITH FENCE LINE TO NORTH  
CENTER OF TELEPHONE RISER N50°E, 50.65 FT.



Signed by *Robert R. Carr*  
ROBERT R. CARR  
Surveyor's Michigan License No. 20704

Date JULY 13, 1993