

SURVEY & REMONUMENTATION

1993

COMMISSION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schonfeldmayer
REGISTER OF DEEDS

002061

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code -#
	MAPLE GROVE	
1. Public Land Survey	T <u>2N</u> R <u>7W</u>	<u>E-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on DECEMBER 7, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

SURVEY BY SETH PRATT, DEPUTY COUNTY SURVEYOR 1882
STAKE: ELM 25" S80°W 87-1/2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO WITNESSES REMAINING
RE-ESTABLISHED CORNER AT OCCUPATION OF OLD FENCE RUNNING WEST AND TREE ROW RUNNING EAST AND CENTERLINE OF NORTH AND SOUTH ROAD AFTER CONFIRMING THIS LOCATION WITH OCCUPATION AT CENTER AND AT SOUTHWEST CORNER OF EAST 1/2 OF NORTHWEST 1/4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PLACED STANDARD BARRY CO REMON. 3/4" ROD AND ALUM. CAP WITH CENTER PUNCH 0.8'± BELOW GRAVEL SURFACE IN LINE WITH TREE ROW RUNNING EAST AND FENCE LINE RUNNING WEST.
NAIL AND REMON. SPOTTER IN WESTERLY SIDE OF 16" ASH S20°W, 35.00 FEET.
NAIL AND REMON. SPOTTER IN ROOT ON SOUTHERLY SIDE OF 12" ASH N79°E, 17.10 FT.
NAIL AND REMON. SPOTTER IN NORHTERLY SIDE OF 10" ELM S80°W, 33.93 FT.



Signed by Robert R. Carr
Surveyor's Michigan License No. 20704

Date JULY 13, 1993