

**SURVEY & REMONUMENTATION**

1993

**COMMISSION**

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmayer

REGISTER OF DEEDS

**002062**

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #
	MAPLE GROVE	
1. Public Land Survey	T <u>2N</u> R <u>7W</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on JANUARY 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

SURVEY OF SECTION 20 BY A.N. BATEMAN COUNTY SURVEYOR 1899.  
FOUND ALL GOVERNMENT CORNERS IN SECTION 20 EXCEPT E 1/4 POST.  
STATES THAT TILE AND STAKES OR STONE, IRON OR BRICK WILL BE FOUND AT CORNERS.  
NO WITNESSES LISTED FOR NORTHEAST CORNER SECTION 20

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

COULD NOT FIND CORNER  
FOUND 4" CAST IRON PIPE AT NORTH 1/4 POST SECTION 20 NO WITNESS REMAINING.  
FOUND 3" X 1/4" CAST IRON STAKE AT NORTHWEST CORNER OF EAST 1/2 OF NORTHWEST 1/4 SECTION 20 AS PER BATEMAN SURVEY (ONE WITNESS REMAINING)  
DOUBLED OVER DISTANCE FROM NORTH 1/4 POST SECTION 20 TO NORTHWEST CORNER EAST 1/2 NORTHWEST 1/4 SECTION 20 TO EAST AND SET NORTHEAST CORNER SECTION 20 ON LINE.  
ACCEPTED THIS LOCATION AS PERPETUATION OF CORNER AS USED BY BATEMAN IN 1899.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

PLACED STANDARD BARRY COUNTY REMON. 3/4" ROD AND ALUM. CAP WITH CENTER PUNCH 0.7'± BELOW GRAVEL SURFACE.  
NAIL AND REMON SPOTTER IN NORTHWESTERLY SIDE OF UTILITY POLE S44°W, 53.10 FT.  
NAIL AND REMON SPOTTER IN SOUTHEASTERLY SIDE OF 10" MAPLE N43°3, 74.70 FT.  
NAIL AND REMON. SPOTTER IN WESTERLY SIDE OF RAILROAD TIE POST S16°E, 33.95 FT.  
7'± EAST OF CENTERLINE ROAD RUNNING NORTH & SOUTH.  
16'± SOUTH OF CENTERLINE ROAD RUNNING EAST & WEST.



Signed by [Signature]  
ROBERT R. CARR  
Surveyor's Michigan License No. 20704

Date JULY 13, 1993