

**SURVEY & REMONUMENTATION**

SEP 14 1999

SECTION

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmayr  
REGISTER OF DEEDS

**002063**

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #:
	MAPLE GROVE	
1. Public Land Survey	T <u>2N</u> R <u>7W</u>	<u>E-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT R. CARR, in a field survey on JANUARY 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

SURVEY OF SECTION 20 BY A.N. BATEMAN, 1899  
SET E-1/4 POST SECTION 20 AT MID-POINT OF WEST SECTION LINE.  
7" ELM S4°E 26.5 FT; 10" OAK S4°E 146.5 FT; 3" ELM N70°E 15.5 FT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO WITNESSES REMAINING.  
NO MONUMENT FOUND.  
RE-SET AT MID-POINT OF WEST SECTION LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY CO REMON 3/4" ROD AND ALUM. CAP WITH CENTER PUNCH.  
15'± EAST OF CENTERLINE OF GRAVEL ROAD  
2' SOUTH OF FENCE LINES RUNNING EAST AND WEST.  
NAIL AND REMON. SPOTTER IN NORTHEASTERLY SIDE OF 10" OAK, S40°E, 7.67 FT.  
NAIL AND REMON. SPOTTER IN NORTHWESTERLY SIDE OF 6" HICKORY S75°W, 36.66 FT.  
NAIL AND REMON SPOTTER IN EASTERLY SIDE OF EASTERLY TREE IN CLUMP OF 10 MAPLES, N16°E, 6.81 FT.

Signed by Robert R. Carr  
Surveyor's Michigan License No. 20704

Date JULY 12, 1993

