

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmarer  
REGISTER OF DEEDS

**002064**

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #/
	MAPLE GROVE	
1. Public Land Survey	T <u>2N</u> R <u>7W</u>	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, ROBERT R. CARR, in a field survey on JANUARY 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
L.C.R.C. NO. 459

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" CAPPED IRON (NO. 12579) AS PER L.C.R.C.  
ANGLE IRON FENCE POST S30°E 33.75 FT TO FACE.  
3" DIAMETER FENCE POST N45°W, 40.86 FT TO FACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
REPLACED FOUND 1/2" IRON WITH STANDARD BARRY CO. REMON. 3/4" ROD AND ALUM. CAP WITH CENTER PUNCH.  
0.5' BELOW GRAVEL SURFACE, IN CENTERLINE OF ROAD TO NORTH.  
2' SOUTH OF CENTERLINE OF EAST/WEST ROAD.  
4' WEST OF FENCE LINE TO SOUTH FACE OF ANGLE IRON POST S04°E, 27.57 FT.  
FACE OF ANGLE IRON POST S31°E, 33.73 FT.  
2" DIA. STEEL POST N40°W, 40.86 FT.



Signed by [Signature]  
ROBERT R. CARR  
Surveyor's Michigan License No. 20704

Date JULY 12, 1993