

**SURVEY & REMONUMENTATION**

SEP 14 1999

**SECTION**

**BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmar  
REGISTER OF DEEDS

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	MAPLE GROVE T <u>2N</u> R <u>7W</u>	F-6	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

**002066**

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on DECEMBER 7, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

SURVEY BY SETH PRATT, DEPUTY COUNTY SURVEYOR 1882  
STAKE; SUGAR MAPLE 8" S3°30'E, .21 ...  
SUGARMAPLE 6" N61°W, .21 ...

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO WITNESSES REMAINING  
ESTABLISHED CENTER AT INTERSECTION OF 1/4 LINE <sup>S</sup> AS RECONSTRUCTED FROM PRATT SURVEY.  
FALLS 0.9 FT WEST OF NORTH AND SOUTH FENCE AND 2.9 FT SOUTH OF EAST AND WEST FENCE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

PLACED STANDARD BARRY CO. REMON. 3/4" ROD AND ALUM. CAP WITH CENTER PUNCH,  
NAIL AND REMON. SPOTTER IN SOUTHEASTERLY  
SIDE OF TWIN 30"-10" MAPLE  
N45°E, 19.35 FT.  
NAIL AND REMON. SPOTTER IN EAST  
SIDE OF 8" BEACH N. 19.85 FT.  
NAIL AND REMON SPOTTER IN  
SOUTHWESTERLY SIDE OF 8" ASH S33°E, 5.63 FT.  
NAIL AND REMON SPOTTER IN NORTHERLY SIDE  
OF 8" ASH S89°W, 24.41 FT.



Signed by [Signature]  
ROBERT R. CARR  
Surveyor's Michigan License No. 20704

Date JULY 13, 1993