

1993

COMMISSION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmayer
REGISTER OF DEEDS

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #
	MAPLE GROVE	
1. Public Land Survey	T <u>2N</u> R <u>7W</u>	<u>F-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

002069

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ROBERT R. CARR, in a field survey on JANUARY 22, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M.D.O.T., 1963, 1/2" PIPE
NORTH 29.35 FT TO FACE OF STEEL FENCE POST
S50°E 39.57 FT TO A 32" ELM
S05°W 29.84 FT TO THE FACE OF STEEL FENCE POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE 0.5 FT DEEP; IN LINE WITH NORTH AND SOUTH FENCES;
IN CENTERLINE OF EAST-WEST ROAD; 4" STEEL POST S04°W, 30.10' TO FACE;
6" STEEL POST NORTH 29.23' TO FACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED FOUND 3/4" PIPE WITH STANDARD BARRY CO REMON 3/4" ROD AND ALU. CAP AND CENTER PUNCH.
0.5± BELOW GRAVEL SURFACE, IN LINE WITH FENCE LINES RUNNING NORTH AND SOUTH.
FACE IF 4" DIA. STEEL POST S08°W, 30.10 FEET.
FACE OF 4" DIA. STEEL POST N06°E, 29.23 FT.
NAIL AND REMON. SPOTTER IN NORTHERLY SIDE OF 30" MAPLE N74°W, 115.85 FT.



Signed by Robert R. Carr
Surveyor's Michigan License No. 20704

Date JULY 12, 1993