

SURVEY & REMONUMENTATION

1993

COMMISSION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmayer
REGISTER OF DEEDS

002070

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In: MAPLE GROVE	Corner Code # G-5
1. Public Land Survey	T <u>2N</u> R <u>7W</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5							⊙						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ROBERT R. CARR, in a field survey on DECEMBER 7, 1992, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SURVEY BY SETH PRATT, DEPUTY COUNTY SURVEYOR 1882
STONE; MAPLE 6" S82°30'W, 2.685 CH; W.O. 3" N0°15'E, 1.39 CH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON STAKE IN LINE WITH OLD FENCES TO NORTH AND SOUTH, AND IN CENTERLINE OF EAST AND WEST ROAD, ACCEPTED AS PERPETUATION OF ABOVE CORNER.
NO WITNESSES REMAINING.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED FOUND 1/2" IRON STAKE WITH STANDARD BARRY CO. REMON 3/4" ROD AND ALUM. CAP WITH CENTER PUNCH.
NAIL AND REMON SPOTTER IN SOUTHEASTERLY SIDE OF 8" PEAR N72°E, 74.09 FT.
NAIL AND REMON SPOTTER IN WESTERLY SIDE OF 15" APPLE S09°W, 37.21 FT.
NAIL AND REMON SPOTTER IN EASTERLY SIDE OF 6" POPLAR N08°E, 29.58 FT. IN LINE WITH FENCE LINES RUNNING NORTH & SOUTH.

Signed by *Robert R. Carr*
Surveyor's Michigan License No. 20704

Date JULY 12, 1993

