

**SURVEY &  
REMONUMENTATION**

1993

**COMMISSION**

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmayer  
REGISTER OF DEEDS

**002071**

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code ##
	<u>MAPLE GROVE</u>	
1. Public Land Survey	T <u>2N</u> R <u>7W</u>	<u>G-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ROBERT R. CARR, in a field survey on DECEMBER 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

SURVEY BY SETH PRATT, DEPUTY COUNTY SURVEYOR 1882  
FLAG LINE AND MEASUREMENT; BEECH 10" S34°30'E, 43.5 LINKS,  
INDICATED POST WAS GONE AND ESTABLISHED LOCATION AT MED-POINT OF EAST SECTION LINE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON WITH CAP (NO. NOT LEDGEABLE) AT MID-POINT OF EAST SECTION LINE IN CULTIVATED FIELD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED FOUND 1/2" IRON WITH STANDARD BARRY CO. REMON 3/4" ROD AND ALUM. CAP WITH CENTER PUNCH.  
IN CULTIVATED FIELD 2'± BELOW SURFACE  
NAIL AND REMON. SPOTTER IN SOUTHERLY SIDE OF 8" MAPLE S80°E, 80.15 FT.  
NAIL AND REMON. SPOTTER IN EASTERLY SIDE OF 8" ELM, N20°E, 47.06 FT.  
NAIL AND REMON. SPOTTER IN NORTHERLY SIDE OF UTILITY POLE S74°W, 106.85 FT.  
CENTERLINE OF NORTH/SOUTH ROAD EAST 51 FT.



Signed by [Signature]  
ROBERT R. CARR  
Surveyor's Michigan License No. 20704

Date JULY 12, 1993