

SURVEY & REMONUMENTATION

1993

COMMISSION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmarer
REGISTER OF DEEDS

002072

Register of Deeds Stamp & File Number

For corners in

BARRY

(County)

Located In:

Corner Code ##

MAPLE GROVE

1. Public Land Survey

T 2N R 7W

G-7

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, ROBERT R. CARR, in a field survey on DECEMBER 7, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SURVEY BY SETH PRATT, DEPUTY COUNTY SURVEYOR 1882

STAKE: BUTTERNUT 16" N65°15'E, .85

ELM 8" N16°W, 2.04

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON STAKE; 6 FT EAST OF CENTERLINE NORTH AND SOUTH ROAD AND IN CENTERLINE OF EAST AND WEST ROAD, NO WITNESSES REMAINING, IN MONUMENT BOX, LARGE STONE UNDER.
ACCEPTED AS PERPETUATION OF CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED FOUND 3/4" IRON STAKE WITH STANDARD BARRY COUNTY REMONUMENTATION 3/4" ROD AND ALUM. CAP WITH CENTER PUNCH.

NAIL AND REMON SPOTTER IN EASTERLY SIDE OF UTILITY POLE, N25°E, 67.78 FT.
NAIL AND REMON SPOTTER IN SOUTHERLY SIDE OF UTILITY POLE, N76°E, 80.87 FT.
NW CORNER OF HOUSE FOUNDATION, S42°E, 75.35 FT.
SW CORNER OF HOUSE FOUNDATION, N55°E, 81.85 FT.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Robert R. Carr

ROBERT R. CARR

Date JULY 12, 1993

Surveyor's Michigan License No. 20704

