

1993

COMMISSION

**BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

JUL 20 3 07 PM '93

Sandy Schondelmaier
REGISTER OF DEEDS

002073

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #
	MAPLE GROVE	
1. Public Land Survey	T <u>2N</u> R <u>7W</u>	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, ROBERT R. CARR, in a field survey on JANUARY 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M.D.O.T. 1963 1/2" PIPE.
S83°E, 47.81 TO A FENCE CORNER POST
N40°W, 108.90 ' TO SOUTHEAST CORNER GRANGE HALL
N75°W, 73.60 TO A P.P.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND LARGE BOLT IN MONUMENT BOX; CENTERLINE M-66; RIGHT-OF-WAY MARKER EAST 50.00 FT;
RIGHT-OF-WAY MAKER WEST 50.0 FT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED FOUND LARGE BOLT WITH STANDARD BARRY COUNTY REMON. 3/4" ROD AND ALUM. CAP WITH CENTER PUNCH.
1'± WEST OF CONST. CENTERLINE OF M-66
CENTER OF CONC. R/W MARKER N85°E, 50.0 FT.
CENTER OF CONC. R/W MARKER S88°W, 50.0 FT.
NAIL AND REMON. SPOTTER IN NORTHERLY SIDE OF UTILITY POLE, N83°W, 71.10 FT.
S.E. CORNER OF OLD GARAGE BUILDING N45°W, 108.42 FT.



Signed by Robert R. Carr
ROBERT R. CARR
Surveyor's Michigan License No. 20704

Date JULY 12, 1993