

DEC 7 2 40 PM '93

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmayer  
REGISTER OF DEEDS

002103

Register of Deeds Stamp & File Number

For corners in

Barry County  
(County)

Maple Grove Township

Located In:

Corner Code #

1. Public Land Survey

T 2N R 7W

J-3

T \_\_\_\_\_ R \_\_\_\_\_

( $\frac{1}{4}$  corner common

T \_\_\_\_\_ R \_\_\_\_\_

to Sections 2

T \_\_\_\_\_ R \_\_\_\_\_

and 11)

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kenneth C. Brandt, in a field survey on September 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: Sugar Maple N.19° W. 12 L.  
16" Sugar Maple S.11° W. 10 L.  
County Surveyor: (1867) set glass & stone  
County Road Comm. fd. seligh runner & Boat Spike  
4" Pine N.75° W. 101.45'  
Steel fence post South 58.7'  
Wood corner post N.25.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Boat Spike 0.4 feet N.N. edge of bituminous pavement.  
Steel fence post stub - 59.7' South  
R.R. Tie corner post - N. 25.55'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed Boat Spike and placed 3/4" Iron pin with Aluminum Remon. Cap & Punch mark - 2" below surface of shoulder.

Nail & Barry County Remon. shiners set as follows:

NW side of 12" Maple S.70° W. 109.95'

SW side of 16" Maple N.60° W. 84.89'

W side of R.R. tie Cor. post N.25.20 feet

SE side 14" Maple N. 35° E. 24.61'

E side Power pole S.15° W. 67.48'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3										●			
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &  
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by

*Kenneth C. Brandt*

Date 11/5/93

Surveyor's Michigan License No. 24587