

SURVEY & REMONUMENTATION

NOV 04 1996

COMMISSION

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

AUG 20 11 27 AM '96

Sandy Schondelmayer
REGISTER OF DEEDS

002392

Register of Deeds Stamp & File Number

For corners in

BARRY

(County)

Located In:

Corner Code *J-4*

- 1. Public Land Survey
CENTER OF SECTION
11 MAPLE GROVE
TOWNSHIP
- 2. Property Controlling
in Section
- 3. Miscellaneous
Property in Sec.
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, **BRIAN REYNOLDS** in a field survey on **12 JULY** 19**95**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET BY THE GENERAL LAND OFFICE.
COUNTY SURVEYOR RECORDS: A.C. WILLSON, NOV. 18, 1867(L.2,P.199), "SET POST BOG ORE & STAKE"
BEECH 12 N31 1/2E 26 1/2 Do. 12 S85 1/2W 21

NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND VERY OLD RAIL ROAD RAIL IN CONCRETE AT INTERSECTION OF NORTH-SOUTH-EAST AND WEST FENCES. WITNESSES BY WILLSON ARE GONE. EXCAVATED AROUND CONCRETE BASE, FOUND NOTHING. BASED ON MEASUREMENTS AROUND SECTION 11, AND COUNTY SURVEYOR RECORDS, ACCEPTED FOUND RAIL ROAD RAIL AS THE CORNER POSITION BY WILLSON. LEFT RAIL ROAD RAIL IN CONCRETE IN PLACE FOR CORNER.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
JULY 10 1995
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

LEFT RAIL ROAD RAIL IN CONCRETE IN PLACE FOR CORNER.
SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 30" BEECH N50°E 12.70'
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A 12" OAK N54°W 27.89'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 16" OAK S42°E 38.44'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 12" OAK S28°E 30.85'
SET 20d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A 16" OAK S2°E 37.34'
CORNER IS THE ANCHOR POST FOR FENCES NORTH-SOUTH-EAST AND WEST



Signed by *Brian Reynolds*
Surveyor's Michigan License No. 31602

Date August 16, 1996