

DEC 7 2 40 PM '93

Sandy Schondelmayer  
 REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

002105

For corners in

Barry County  
(County)

Located In:

Corner Code #

Maple Grove Township

K-7

1. Public Land Survey

T 2N R 7W

(Section corner  
 common to Sec-  
 tions 13, 14,  
 23 & 24)

2. Property Controlling  
 in Section

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
 Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	10	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kenneth C. Brandt in a field survey on September 6, 19 93  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: 10" Beech N.82½° E. 22 L  
 20" Beech S.41° W. 15 L

Boat spike as described in L.C.R.C. #4101 dated 4/5/90 by K.D. Fluke who indicated it was in  
 accord with County Surveyor survey (1876) as runout of Section revealed.

(No witness found from GLO)

P. Pole N.42° W. 61.17' ; Tel. Riser N.47° E. 63.29' ;  
 Fence cor. N.42° E. 43.56' ; Iron & Cap S.45° E. 46.41' ; ½" Iron & cap. N.45° E. 47.04'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Boat spike 1' South of center of East-West Road & 1' E. of center of North-South road.

Tel. Riser N.47° E. 63.29'  
 Iron & Cap S.45° E. 46.4'

SURVEY &  
 REMONUMENTATION

APR 05 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed Boat spike and replaced with 3/4" Iron pin and aluminum Remon. Cap with punch mark  
 2" below pavement surface.

Nail & Barry County Remon. shiners set as follows:

S.W. side of U. Pole N.42° W. 61.10 feet  
 East side of U. Pole N.15° W. 226.42 feet  
 West side of U. Pole N.15° E. 215.15 feet  
 SE side of U. Pole N.45° E. 63.19 feet



Signed by Kenneth C. Brandt

Date 11/5/93

Surveyor's Michigan License No. 24587