

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

APR 04 2000

For Corners in
BARRY
(county)

Located In: _____ Corner Code # _____

SECTION _____

1. Public Land Survey T 2N R 7W K-9
CORNER COMMON TO T _____ R _____
SECTIONS 23, 24, 25 & 26 T _____ R _____
MAPLE GROVE TOWNSHIP T _____ R _____



2852
Page: 1 of 1
12/27/1999 01:44P

Daria K. Burghdoff - Barry Co. LCRCR

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 9 JULY, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R7W, P.57) A BE. 20 S64E 15 W.O. 8 N33W 20
 - NO MENTION OF THIS CORNER COULD BE FOUND IN THE COUNTY SURVEYOR RECORDS.
 - ACT 132 SURVEY: BY THOMAS E. JOINER, P.S. # 18435, 31 JAN., 1983 (L.1, P.737) "SET R.R. SPIKE ON ROAD CENTERLINES EXTENDED" CL ROAD SOUTH 49.00' STOP SIGN SSE. 95.60' STOP SIGN W. 17.6'

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER **

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND RAILROAD SPIKE AS RECITED IN ITEM #3 ABOVE. TRAVERSED ALL OF SECTION 25, TYING OCCUPATION. EXCAVATION UNDER RAILROAD SPIKE REVEALED NOTHING. POSITION OF RAIL ROAD SPIKE CONFORMS WITH CORNERS SOUTH, EAST AND WITH 1/8 LINE OCCUPATION.
ACCEPTED FOUND RAIL ROAD SPIKE AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.
REPLACED FOUND RAIL ROAD SPIKE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AND INSTALLED MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 24" IRON) WITH ALUMINUM CAP, INSTALLED MONUMENT BOX.
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A 6" WILLOW N63°W 65.76'
NORTHWEST CORNER OF A HOUSE FOUNDATION S30°E 253.19'
NORTHEAST CORNER OF A HOUSE FOUNDATION S40°E 290.12'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 4" TWIN OAK N67°E 69.78'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 3" TWIN OAK N89°E 77.83'

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON
12 July, 99 BR
 BRIAN REYNOLDS COUNTY SURVEYOR



Signed by *Brian Reynolds*
 Surveyor's Michigan License No 31602

Date DEC 27, 1999