

**BARRY COUNTY REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

APR 04 2000

For Corners in BARRY Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(county)

SECTION \_\_\_\_\_

1. Public Land Survey T 2N R 7W \_\_\_\_\_ K-10  
1/4 CORNER COMMON TO T \_\_\_\_\_ R \_\_\_\_\_  
SECTIONS 25 & 26 T \_\_\_\_\_ R \_\_\_\_\_  
MAPLE GROVE TOWNSHIP T \_\_\_\_\_ R \_\_\_\_\_



**2853**  
Page: 1 of 1  
12/27/1999 01:44P

Darla K. Burghdoff - Barry Co. LGRCR

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Brian Reynolds, in a field survey on 9 JULY, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R7W, P.57) A SUGAR 9 S58E 28 Do. 6 N78 1/2W 32
- COUNTY SURVEYOR RECORDS: SETH PRATT, 1885 (L.1, P.324) SUGAR 14 N81 1/2W 55 1/2 CHERRY S37W 1.05 1/2
- ACT 132 SURVEY: BY THOMAS E. JOINER, P.S. #18435, 31 JANUARY, 1983 (L.1, P.737) "SET 1/2" ROD ON CENTERLINE OF ROAD & FENCE LINES E & W" MAPLE CLUMP ENE. 23.00' POWER P. SE. 41.06' 14" MAPLE SW. 87.85' FENCE P. W. 33.71'

\*\*\* NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER \*\*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**FOUND 1/2" IRON AND MAPLE CLUMP WITNESS RECITED BY JOINER (ITEM #3 ABOVE). EXCAVATION REVEALED NOTHING. TRAVERSED OF SECTION 25, TYING OCCUPATION. FOUND 1/2" IRON CONFORMS WELL WITH MEASUREMENTS TO CORRESPONDING CORNERS AND OCCUPATION. ACCEPTED FOUND 1/2" IRON AS BEST AVAILABLE EVIDENCE OF CORNER POSITION. REPLACED 1/2" IRON WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.**


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 14" MAPLE S16°W 103.90'
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A RAIL ROAD TIE FENCE CORNER POST S88°W 33.96'
- FOUND NAIL IN THE NORTHWEST SIDE OF A 10" MAPLE CLUMP N77°E 23.02'
- FOUND NAIL IN THE NORTHEAST SIDE OF A UTILITY POLE N38°E 41.08'

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

12 July '99  
BRIAN REYNOLDS

BR  
COUNTY SURVEYOR



Signed by [Signature]  
Surveyor's Michigan License No 31602

Date DEC 27, 1999