

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

APR 04 2000

For Corners in BARRY Located In: _____ Corner Code # _____
(county)

SECTION _____

1. Public Land Survey T 2N R 7W L-9
1/4 CORNER COMMON TO T _____ R _____
SECTIONS 24 & 25 T _____ R _____
MAPLE GROVE TOWNSHIP T _____ R _____



2855
Page: 1 of 1
12/27/1999 01:44P

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 09 JULY, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE: MUSGROVE EVANS, D.S., 1826 (R7W, P.58) CHERRY 12 S49W 22 Be. 14 N40E 20
- COUNTY SURVEYOR RECORDS: FRANK BOWEN, 18 JANUARY, 1876 (L-1, P.130) "FOUND STONE FOR CORNER" NO WITNESSES GIVEN

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" X 6" RAILROAD SPIKE 1' BELOW ROAD GRADE. FURTHER EXCAVATION TO A DEPTH OF 2.5' REVEALED THREE STONES. THE THREE STONES FORM A CRUDE TRIANGLE BEING 0.9' APART. FURTHER EXCAVATION REVEALED NOTHING. TRAVERSED ALL OF SECTION 25, TYING OCCUPATION. HELD POSITION OF LARGEST STONE, N45°W± 0.9' FROM FOUND SPIKE, FOR CORNER. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AND INSTALLED MONUMENT BOX.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP. CHISELED DRILL HOLE IN THE TOP CENTER OF A CONCRETE FILLED PIPE CORNER POST N30°E 40.26'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 10" WALNUT N07°E 82.28'
SET 20d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A UTILITY POLE S79°W 171.90'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 12" POPLAR S64°W 173.78'
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A UTILITY POLE S53°W 69.66'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

12 July '99
BRIAN REYNOLDS

BR
COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date DEC 27, 1999