

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &
REMONUMENTATION

For Corners in
BARRY
(county)

Located In: Corner Code #

APR 04 2000

SECTION

1. Public Land Survey
CENTER 1/4 CORNER
SECTION 25
MAPLE GROVE TOWNSHIP

T 2N R 7W L-10
T _____ R _____
T _____ R _____
T _____ R _____



2856

Page: 1 of 1
12/27/1999 01.44P

Darla K. Burghdoff - Barry Co. LCROR

Register of Deeds Stamp & File Number

2. Property Controlling
in Section

S _____ T _____ R _____
S _____ T _____ R _____

3. Miscellaneous

S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 09 JULY, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
2. NO MENTION OF THIS CORNER COULD BE FOUND IN THE RECORDS OF THE COUNTY SURVEYOR.

*** NO HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO MAGNETIC EVIDENCE OF CORNER POSITION.
TRAVERSED ALL OF SECTION 25, TYING IN OCCUPATION.
SET BARRY COUNTY REMONUMENTATION MONUMENT AT INTERSECTION OF 1/4 LINES.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF AN 18" MAPLE N72°W 16.69'
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A 10" TWIN MAPLE N14°E 10.46'
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 12" ELM S25°E 10.74'
- SET 20d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF AN 18" MAPLE S18°W 21.99'
- SET 20d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A 14" MAPLE S40°W 13.56'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

12 July '99
BRIAN REYNOLDS

BR
COUNTY SURVEYOR



Signed by *Brian Reynolds*
Surveyor's Michigan License No. 31602

Date DEC 27, 1999